

CODED NO.	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE		
				(25-3,4)R		(25-3)PB
				ROADWAY 0003		BRIDGE SN 025-6010 0008
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	875	875		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	460	460		
20100500	TREE REMOVAL, ACRES	ACRE	8.75	8.75		
20200100	EARTH EXCAVATION	CU YD	111235	111235		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2789	2789		
20400800	FURNISHED EXCAVATION	CU YD	16680	16680		
20800150	TRENCH BACKFILL	CU YD	5895	5895		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	149290	149290		
* 25000200	SEEDING, CLASS 2	ACRE	38	38		
* 25000300	SEEDING, CLASS 3	ACRE	1.25	1.25		
* 25000350	SEEDING, CLASS 7	ACRE	51	51		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3533	3533		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3533	3533		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3533	3533		
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	2.5	2.5		
* 25000750	MOWING	ACRE	39.25	39.25		
* 25100115	MULCH, METHOD 2	ACRE	39.25	39.25		
* 25100630	EROSION CONTROL BLANKET	SQ YD	15274	15274		
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	120	120		
28000305	TEMPORARY DITCH CHECKS	FOOT	5249	5249		
28000400	PERIMETER EROSION BARRIER	FOOT	10570	10570		
28000500	INLET AND PIPE PROTECTION	EACH	172	172		
28001000	AGGREGATE (EROSION CONTROL)	TON	18	18		
28100105	STONE RIPRAP, CLASS A3	SQ YD	388	388		
28100107	STONE RIPRAP, CLASS A4	SQ YD	10002	10002		
28100109	STONE RIPRAP, CLASS A5	SQ YD	7058	7058		
28200200	FILTER FABRIC	SQ YD	17060	17060		
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	223633	223633		
30201250	PROCESSING MODIFIED SOIL 24"	SQ YD	28901	28901		
30201500	LIME	TON	7091	7091		
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	252420	252420		
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	3472	3153		319
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	88	88		
40600300	AGGREGATE (PRIME COAT)	TON	2	2		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	415	415		
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	70	70		
42000100	PORTLAND CEMENT CONCRETE PAVEMENT 6"	SQ YD	319			319
42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SQ YD	14726	14726		
42000511	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	SQ YD	6147	6147		
42000540	PORTLAND CEMENT CONCRETE PAVEMENT 12"	SQ YD	37057	37057		
42001200	PAVEMENT FABRIC	SQ YD	55052	54733		319
42001300	PROTECTIVE COAT	SQ YD	92806	92806		
42100360	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 13"	SQ YD	202070	202070		

CODED NO.	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE		
				(25-3,4)R		(25-3)PB
				ROADWAY 0003		BRIDGE SN 025-6010 0008
42100615	PAVEMENT REINFORCEMENT	SQ YD	202070	202070		
42101300	PROTECTIVE COAT	SQ YD	202070	202070		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	20269	20269		
44000100	PAVEMENT REMOVAL	SQ YD	110808	110808		
44001980	CONCRETE BARRIER REMOVAL	FOOT	826	826		
44004000	PAVED DITCH REMOVAL	FOOT	568	568		
44004250	PAVED SHOULDER REMOVAL	SQ YD	47725	47725		
44201839	CLASS D PATCHES, TYPE II, 16 INCH	SQ YD	11	11		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	100	100		
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	2902	2902		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	40	40		
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	689	689		
48300800	PORTLAND CEMENT CONCRETE SHOULDERS 13"	SQ YD	17676	17676		
50102400	CONCRETE REMOVAL	CU YD	19.2	19.2		
50104400	CONCRETE HEADWALL REMOVAL	EACH	4	4		
50105220	PIPE CULVERT REMOVAL	FOOT	1070	1070		
50200100	STRUCTURE EXCAVATION	CU YD	1886			1886
50300225	CONCRETE STRUCTURES	CU YD	115			115
50300255	CONCRETE SUPERSTRUCTURE	CU YD	455.1			455.1
50300300	PROTECTIVE COAT	SQ YD	1253.3			1253.3
50300285	FORM LINER TEXTURED SURFACE	SQ FT	3198			3198
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1
50500505	STUD SHEAR CONNECTORS	EACH	954			954
50800105	REINFORCEMENT BARS	POUND	18100	18100		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	90320	620		89700
50800515	BAR SPLICERS	EACH	46			46
51100100	SLOPE WALL 4 INCH	SQ YD	144	130		14
51201800	FURNISHING STEEL PILES HP14X73	FOOT	384			384
51202305	DRIVING PILES	FOOT	248			248
51203800	TEST PILE STEEL HP14X73	EACH	2			2
51204650	PILE SHOES	EACH	10			10
51500100	NAME PLATES	EACH	1			1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	30			30
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	6			6
52100520	ANCHOR BOLTS, 1"	EACH	18			18
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	2	2		
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	2	2		
54001003	BOX CULVERT END SECTION, CULVERT NO. 3	EACH	2	2		
54001004	BOX CULVERT END SECTION, CULVERT NO. 4	EACH	2	2		
54002020	EXPANSION BOLTS 3/4 INCH	EACH	46	46		
54003000	CONCRETE BOX CULVERTS	CU YD	82.1	82.1		
54010402	PRECAST CONCRETE BOX CULVERT 4' X 2'	FOOT	53	53		
54010403	PRECAST CONCRETE BOX CULVERT 4' X 3'	FOOT	88	88		

† NON-PARTICIPATING (100% STATE)

\* SPECIALTY ITEM

FILE NAME =  
S:\Project\183\183-70\Map\183-70.dwg

USER NAME = betaj  
PLOT SCALE = 100.0000' / IN.  
PLOT DATE = 3/24/2011

DESIGNED - ESW	REVISED - 3-24-11
DRAWN - ESW	REVISED -
CHECKED - BRM	REVISED -
DATE - 5-12-08	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES, FAI ROUTE 57/70**

SCALE: SHEET NO. 1 OF 4 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/70	(25-3,4)R AND (25-3)PB	EFFINGHAM	1098	5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 74299	