

PIPE CULVERTS SCHEDULE

LOCATION		PIPE CULVERTS, CLASS A, TYPE 1 24"	PIPE CULVERTS, CLASS A, TYPE 1 36"	PIPE CULVERTS, CLASS A, TYPE 1 72"	PIPE CULVERTS, CLASS A, TYPE 2 42"	PIPE CULVERTS, CLASS A, TYPE 2 84"	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 72"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 84"	INSERTION CULVERT LINER 72"	CONCRETE COLLAR (CU YD)	CONCRETE THRUST BLOCKS (EACH)	REMOVE AND RELAY END SECTIONS (EACH)	CONCRETE ANCHORS (EACH)	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 24" (SPECIAL) (EACH)	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 36" (SPECIAL) (EACH)
STATION	SIDE	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)	(FOOT)	(CU YD)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)
I-57/70																		
2128+25.69	LT/RT			12						2			1.8					
2129+04.63	LT	2											0.4		1			
2142+05.34	RT	2											0.8		1			
2158+25.00	LT							1										
2160+00.00 TO 2160+50.00	RT													2		5		
2160+75.00	LT								1									
2161+35.19 TO 2161+89.65	LT													2		4		
2162+03.42	LT/RT					21						237	2.2					
2177+18.85	LT	6											0.8		1			
2195+50.00	LT												0.4					
2213+99.75	LT/RT				39								1.2		2			
2221+50.00	RT								1									
2238+00.00	LT												0.4					
2248+00.00	RT								1									
2254+00.00	CENTER												0.4					
2269+05.00	RT								1									
FAYETTE RAMP A																		
10+00.24	RT																	
12+02.00	LT/RT	128																
FAYETTE RAMP B																		
18+81.50	RT								1									
KELLER RAMP C																		
16+55.31	RT								1									
18+44.43	LT/RT		132															2
KELLER RAMP D																		
19+64.88	LT/RT						10						1		2			
21+34.09	RT																	
TOTAL		138	132	12	39	21	10	5	4	2	2	237**	9.4*	4*	7	9*	2	2

* NOT A TOTAL QUANTITY
** SEE SHEET 417 FOR CULVERT DETAILS.

DRAINAGE REMOVAL SCHEDULE

LOCATION			PIPE CULVERT REMOVAL (FOOT)	CONCRETE HEADWALL REMOVAL (EACH)	REMOVING MANHOLES (EACH)	REMOVING INLETS (EACH)	STORM SEWER REMOVAL (FOOT)	REMOVAL OF PRECAST FLARED END SECTION (EACH)
STATION TO STATION	OFFSET	SIDE	(FOOT)	(EACH)	(EACH)	(EACH)	(FOOT)	(EACH)
I-57/70								
2123+71.17 TO 2124+96.25	0.0	CENTER					125	
2123+72.00	0.0	CENTER			1			
2128+25.69	VAR.	LT/RT		2				
2129+04.62	0.0	CENTER				1		
2142+05.34	0.0	CENTER				1		
2156+85.40	0.0	CENTER	14			1		
2162+03.41	VAR.	LT/RT		2				
2177+18.85	0.0	CENTER				1		
2195+49.39	0.0	CENTER				1		
2197+01.17 TO 2198+57.57	VAR.	RT					155	
2197+03.98	67.5	RT				1		
2198+57.57	69.2	RT				1		
2198+57.57 TO 2200+73.71	VAR.	RT					214	
2199+07.18 TO 2202+83.89	0.0	CENTER	377					2
2200+73.71 TO 2201+10.85	VAR.	RT					35	
2200+75.00	72.6	RT			1			
2201+10.85	69.1	RT				1		
2201+10.85 TO 2203+64.45	VAR.	RT					252	
2203+64.45	69.2	RT				1		
2203+64.45 TO 2206+70.97	VAR.	RT			1		304	
2206+70.97	66.2	RT						
2206+70.97 TO 2212+28.67	VAR.	RT					556	
2213+99.75	0.0	CENTER	8			1		
2221+98.98	7.6	RT				1		1
2237+99.19	0.0	CENTER				1		
2247+61.22 TO 2250+30.63	0.0	CENTER	270					
2247+99.61 TO 2249+52.87	0.0	RT	151					
2254+00.06	0.0	CENTER				1		
FAYETTE RAMP A								
11+54.86	VAR.	RT	6			1		1
EX FAYETTE RAMP B								
2+45.81	VAR.	LT/RT	45			1		1
KELLER RAMP C								
12+82.23	9.7	LT				1	48	
13+82.39	16.8	LT				1	55	
14+31.65	16.0	LT				1	51	
15+81.97	14.5	LT				1	52	
17+65.65	12.1	LT				1	43	
18+53.05		LT	99					2
18+61.02		LT	100					2
TOTAL			1070	4	3	20	1890	9

TEMPORARY DRAINAGE SCHEDULE

LOCATION		PIPE CULVERTS, CLASS D, TYPE 1 15" (TEMPORARY) (FOOT)	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY) (FOOT)	TEMPORARY MANHOLE (EACH)
STATION	ROADWAY	(FOOT)	(FOOT)	(EACH)
0+95	FAY RAMP A CONNECTOR	62		
1+18	FAY RAMP A CONNECTOR		45	
1+20	FAY RAMP A CONNECTOR		5	
1+22	FAY RAMP A CONNECTOR			1
1+00	FAY RAMP B CONNECTOR	50		
1+40	FAY RAMP C CONNECTOR	85		
1+40	FAY RAMP D CONNECTOR	60		
1+00	KEL RAMP A CONNECTOR	80		
0+85	KEL RAMP C CONNECTOR	55		
0+75	KEL RAMP D CONNECTOR	65		
TOTAL		457	50	1

PIPE DRAINS SCHEDULE

LOCATION		PIPE CULVERTS, CLASS D, TYPE 1 15" (FOOT)	PIPE DRAINS 15" (FOOT)	PIPE DRAINS 24" (FOOT)	CONCRETE THRUST BLOCKS (EACH)	CONCRETE ANCHORS (EACH)	METAL END SECTIONS 15" (EACH)	METAL END SECTIONS 24" (EACH)
STATION	SIDE	(FOOT)	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)
I-57/70								
2160+00.00 TO 2160+50.00	RT			79				2
2161+35.19 TO 2161+89.65	LT			63				2
BIKE TRAIL								
13+65	LT/RT	43					2	
24+06	RT		57		1	4	1	
TOTAL		43	57	142	1*	4*	3	4

* NOT A TOTAL QUANTITY

TEMPORARY PAVEMENT SCHEDULE

LOCATION		PORTLAND CEMENT CONCRETE PAVEMENT 12" (SQ YD)	PROTECTIVE COAT (SQ YD)	PAVEMENT FABRIC (SQ YD)	PAVEMENT REMOVAL (SPECIAL) (SQ YD)	CLASS D PATCHES, TYPE II, 16 INCH (SQ YD)
STATION TO STATION	ROADWAY	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)
PRE-STAGE 1						
STA 2121+44.00 TO STA 2268+00.00	I-57/70	23012	23012	23012	23012	
STA 2268+00.00 TO STA 2286+00.00	I-57/70	3873	3873	3873		
STA 2269+05.00	I-57/70					11
STAGE 1						
STA 2204+96.43 TO STA 2206+73.95	I-57/70	177	177	177		
STA 2268+00.00 TO STA 2280+95.00	I-57/70	3088	3088	3088		
PRE-STAGE 2A						
STA 2134+15.00 TO STA 2217+40.00	I-57/70	3679	3679	3679	3679	
PRE-STAGE 2B						
STA 2137+88.06 TO STA 2213+88.31	I-57/70	1792	1792	1792	1792	
STA 19+65.55 TO STA 26+61.72	KELLER RAMP A	1078	1078	1078	1078	
STA 19+98.39 TO STA 24+86.40	KELLER RAMP C	358	358	358	358	
TOTAL		37057	37057*	37057*	29919	11

*NOT A TOTAL QUANTITY

RIPRAP SCHEDULE

LOCATION		STONE RIPRAP CLASS A3 (SQ YD)	STONE RIPRAP CLASS A4 (SQ YD)	STONE RIPRAP CLASS A5 (SQ YD)	FILTER FABRIC (SQ YD)
STATION TO STATION	SIDE	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)
I-57/70					
2128+21.03 TO 2128+31.03	LT		28		28
2156+42.12 TO 2157+18.57	RT		191		191
2159+25.00 TO 2161+36.42	LT		484		484
2160+46.20 TO 2160+60.30	RT		11		11
2161+79.04 TO 2175+50.00	LT			7058	7058
2162+50.00 TO 2163+50.00	RT		178		178
2163+50.00 TO 2163+75.00	RT	37			
2166+75.00 TO 2169+10.00	RT		547		547
2169+50.00 TO 2174+00.00	RT		3518		3518
2174+23.00 TO 2174+50.00	RT		36		36
2174+50.00 TO 2174+75.00	RT	34			
2175+50.00 TO 2192+00.00	LT		3698		3698
2193+25.00 TO 2193+85.00	LT	141			
2193+85.00 TO 2194+05.00	LT		46		46
2198+05.87 TO 2198+36.56	LT		97		97
2213+86.76 TO 2214+08.29	RT		58		58
2244+07.73 TO 2244+23.00	RT		75		75
FAYETTE RAMP B					
16+75.00 TO 17+70.00	RT	176			
KELLER RAMP C					
17+74.00 TO 19+76.00	RT		361		361
KELLER RAMP D					
18+00.00 TO 21+32.63	RT		674		674
TOTAL		388	10002	7058	17060