


MATCH LINE STA. 2159+00.00

FAYETTE RAMP A						
POINT	ELEVATION	NORTHING	EASTING	ROADWAY STATION	ROADWAY OFFSET	RAMP STATION
FAYETTE RAMP A						
100	571.27	894,634.31	917,629.53			11+00.00
101	570.91	894,657.01	917,640.01			10+75.00
102	570.60	894,680.13	917,649.52			10+50.00
103	570.35	894,703.63	917,658.04			10+25.00
104	570.16	894,727.19	917,666.38			10+00.00
105	570.01	894,750.99	917,674.04			9+75.00
106	569.93	894,774.79	917,681.69			9+50.00
107	569.88	894,798.59	917,689.35			9+25.00
108	569.84	894,822.39	917,697.00			9+00.00
109	569.80	894,846.19	917,704.66			8+75.00
110	569.77	894,859.74	917,709.01			8+60.77
WB FAI ROUTE 57/70						
111	569.69	894,883.59	917,716.69	2158+75.00	88.27	8+34.71

FAYETTE RAMP B						
POINT	ELEVATION	NORTHING	EASTING	ROADWAY STATION	ROADWAY OFFSET	RAMP STATION
FAYETTE RAMP B						
200	571.38	894,468.74	917,809.42			18+25.00
201	571.11	894,493.74	917,809.94			18+50.00
202	570.89	894,518.69	917,811.41			18+75.00
203	570.74	894,543.60	917,813.45			19+00.00
204	570.63	894,568.42	917,816.43			19+25.00
205	570.54	894,593.13	917,820.23			19+50.00
206	570.44	894,617.70	917,824.83			19+75.00
207	570.35	894,642.12	917,830.19			20+00.00
EB FAI ROUTE 57/70						
208	570.32	894,649.28	917,831.81	2156+75.00	79.52	20+07.34
209	570.24	894,673.67	917,837.31	2157+00.00	79.04	20+32.35
210	570.16	894,698.06	917,842.82	2157+25.00	78.56	20+57.35
211	570.08	894,722.46	917,848.33	2157+50.00	78.08	20+82.36
212	570.01	894,746.85	917,853.84	2157+75.00	77.60	21+07.36
213	569.94	894,771.24	917,859.35	2158+00.00	77.12	21+32.37
214	569.88	894,795.63	917,864.85	2158+25.00	76.63	21+57.37
215	569.82	894,820.02	917,870.36	2158+50.00	76.15	21+82.37
216	569.75	894,844.41	917,875.87	2158+75.00	75.67	22+07.38



FILE NAME =
 USER NAME = bsoebel
 PLOT SCALE = 48.0000" / IN.
 PLOT DATE = 3/17/2011

DESIGNED - ESW
 DRAWN - PDB
 CHECKED - BRM
 DATE - 4-23-08

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

PAVEMENT ELEVATION DETAIL, RAMP A AND B, FAYETTE AVE.

SCALE: 1"=20' SHEET NO. 4 OF 5 SHEETS STA. 2154+50.00 TO STA. 2159+00.00

F.A.I. RTE. 57/70	SECTION (25-3,4)R	COUNTY EFFINGHAM	TOTAL SHEETS 1098	SHEET NO. 200
CONTRACT NO. 74299				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				