


KELLER RAMP C						
POINT	ELEVATION	NORTHING	EASTING	ROADWAY STATION	ROADWAY OFFSET	RAMP STATION
EB FAI ROUTE 57/70						
700	573.39	896,875.99	918,369.31	2179+67.69	66.00	10+00.00
701	573.45	896,882.94	918,371.34	2179+75.00	66.09	10+07.24
702	573.67	896,906.71	918,378.29	2180+00.00	66.32	10+32.00
703	573.88	896,930.47	918,385.23	2180+25.00	66.46	10+56.76
704	574.10	896,954.19	918,392.32	2180+50.00	66.66	10+81.52
705	574.30	896,977.83	918,399.69	2180+75.00	67.08	11+06.28
706	574.51	897,001.38	918,407.35	2181+00.00	67.69	11+31.04
707	574.70	897,024.84	918,415.29	2181+25.00	68.52	11+55.81
708	574.89	897,048.20	918,423.52	2181+50.00	69.56	11+80.58
709	575.08	897,071.47	918,432.03	2181+75.00	70.81	12+05.36
710	575.25	897,094.64	918,440.83	2182+00.00	72.27	12+30.14
711	575.42	897,117.71	918,449.90	2182+25.00	73.93	12+54.93
712	575.59	897,140.68	918,459.26	2182+50.00	75.81	12+79.73
713	575.75	897,163.59	918,468.74	2182+75.00	77.73	13+04.53
714	575.92	897,186.48	918,478.22	2183+00.00	79.56	13+29.31



FILE NAME =	USER NAME = bseibel	DESIGNED - ESW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT ELEVATION DETAIL, RAMP D AND C, KELLER AVE.			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
S:\Projects\183-00072-57-70\pav\keller\pav.dwg		DRAWN - PDB	REVISED -					57/70	(25-3,4R)	EFFINGHAM	1098	219			
		CHECKED - BRM	REVISED -					SCALE: 1"=20'			SHEET NO. 1 OF 7 SHEETS			CONTRACT NO. 74299	
		DATE - 4-23-08	REVISED -					STA. 2178+00.00 TO STA. 2183+00.00			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				