

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		90% FEDERAL 10% STATE		100% STATE 0005	CODE NO	ITEM	UNIT		90% FEDERAL 10% STATE		100% STATE 0005
20200500	EARTH EXCAVATION (WIDENING)	CU YD	3729		3729	50104650	SLOPE WALL REMOVAL	SQ YD	611		611		
20300100	CHANNEL EXCAVATION	CU YD	809		809	50157300	PROTECTIVE SHIELD	SQ YD	360		360		
20700220	POROUS GRANULAR EMBANKMENT	CU YD	772	263	509	50300255	CONCRETE SUPERSTRUCTURE	CU YD	206.2		206.2		
28100103	STONE RIPRAP, CLASS A2	SQ YD	194	194		50300260	BRIDGE DECK GROOVING	SQ YD	2913		2913		
28100105	STONE RIPRAP, CLASS A3	SQ YD	43		43	50300300	PROTECTIVE COAT	SQ YD	4286	2940	1346		
28100107	STONE RIPRAP, CLASS A4	SQ YD	1315	1315		50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	37430		37430		
<del>28200200</del>	<del>FILTER FABRIC</del>	<del>SQ YD</del>	<del>1515</del>	<del>1515</del>		50606701	CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 1	L SUM	1		1		
31100300	SUBBASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	15890		15890	50606702	CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 2	L SUM	1		1		
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	370		370	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	31480		31480		
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	619		619	50800515	BAR SPLICERS	EACH	208		208		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	152.4	115.1	37.3	51100100	SLOPE WALL 4 INCH	SQ YD	611		611		
40600300	AGGREGATE (PRIME COAT)	TON	578.2	526.2	52	52000110	PREFORMED JOINT STRIP SEAL	FOOT	819		819		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	12349	12082	267	52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	132		132		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	3292	3292		52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	24		24		
40600990	TEMPORARY RAMP	SQ YD	5103	5103		52100520	ANCHOR BOLTS, 1"	EACH	312		312		
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	9050		9050	54213459	END SECTIONS 24"	EACH	2	2			
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	12634	12634		54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2			
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	333		333	54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1			
40603345	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1810		1810	54248510	CONCRETE COLLAR	CU YD	17	17			
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	421		421	54390180	INSERTION CULVERT LINER 24"	FOOT	279	279			
44000100	PAVEMENT REMOVAL	SQ YD	15890		15890	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	360	360			
44001980	CONCRETE BARRIER REMOVAL	FOOT	3803	3803		550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	22	22			
44022025	PARTIAL DEPTH REMOVAL 2"	SQ YD	16188	16188		55101200	STORM SEWER REMOVAL 24"	FOOT	28	28			
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SQ YD	492	492		58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	4947		4947		
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SQ YD	231	231		60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	27	27			
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SQ YD	346	346		60100074	SHOULDER REMOVAL AND REPLACEMENT 8"	FOOT	40029	40029			
44213000	PATCHING REINFORCEMENT	SQ YD	947	947		60107700	PIPE UNDERDRAINS 6"	FOOT	39459	39459			
44213200	SAW CUTS	FOOT	5490	5490		60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	1000	1000			
44213204	TIE BARS 3/4"	EACH	127	127		60237420	INLETS, TYPE A, TYPE 20 FRAME AND GRATE	EACH	45	45			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	3836	3836		60240324	INLETS, TYPE B, TYPE 20 FRAME AND GRATE	EACH	2	2			
48203100	HOT-MIX ASPHALT SHOULDERS	TON	13561	13561		60260100	INLETS TO BE ADJUSTED	EACH	100	96	4		
50102400	CONCRETE REMOVAL	CU YD	187.8	2	185.8	60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	675	675			
50104400	CONCRETE HEADWALL REMOVAL	EACH	27	27		*63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	4387.5	4387.5			

\* SPECIALTY ITEM

FILE NAME =	USER NAME = burnsideem	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	DRAWN -	REVISED -	F.A.I. RTE. 64	SECTION 82-(3,4)RS	COUNTY ST. CLAIR	TOTAL SHEETS 167	SHEET NO. 5	
		CHECKED -	REVISED -			CONTRACT NO. 76415							
		DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							
PLOT SCALE = 50.0000' / 1"		PLOT DATE = 11/29/2011				SCALE: _____		SHEET NO. _____ OF _____ SHEETS		STA. _____ TO STA. _____			