

SUMMARY OF QUANTITIES

| SUMMARY OF QUANTITIES | | | URBAN TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | | SUMMARY OF QUANTITIES | | | URBAN TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | |
|-----------------------|--|--------|------------------------------|----------------------------------|------|--------------------|---|-------|--------|------------------------------|----------------------------------|------|--------------------|
| CODE NO | ITEM | UNIT | | 90% FEDERAL 10% STATE 0005 | 0014 | 100% STATE 0005 | CODE NO | ITEM | UNIT | | 90% FEDERAL 10% STATE 0005 | 0014 | 100% STATE 0005 |
| 84200500 | REMOVAL OF LIGHTING UNIT, SALVAGE | EACH | 8 | | | Z0012130 | BRIDGE DECK SCARIFICATION 3/4" | SQ YD | 2660 | | 2660 | | |
| 89502350 | REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT | FOOT | 870 | 870 | | Z0012166 | BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 3/4" | SQ YD | 2660 | | 2660 | | |
| X0322194 | POLYMER MODIFIED PORTLAND CEMENT MORTAR | SQ FT | 14 | | 14 | Z0012754 | STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES) | SQ FT | 306 | | 306 | | |
| X0323491 | SLOPE WALL CRACK SEALING | FOOT | 48 | | 48 | Z0012755 | STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES) | SQ FT | 55 | | 55 | | |
| X0323833 | DYNAMIC MESSAGE SIGN | EACH | 4 | | 4 | Z0015802 | PLUG EXISTING DECK DRAINS | EACH | 20 | | 20 | | |
| X0325279 | CLASS SI CONCRETE (MISCELLANEOUS) | CU YD | 19 | 19 | | Z0018302 | DRAINAGE STRUCTURES, TYPE 1 (SPECIAL) | EACH | 47 | 47 | | | |
| X0325893 | CLEAN EXISTING END SECTION | EACH | 2 | | | Z0021908 | SILICONE JOINT SEALER, 2" | FOOT | 84 | | 84 | | |
| X0326677 | REMOVE HIGH TENSION CABLE MEDIAN BARRIER | FOOT | 7731 | 7731 | | XZ0029652 | HIGH TENSION CABLE MEDIAN BARRIER | FOOT | 6885 | 6885 | | | |
| X0502600 | TEMPORARY LIGHTING | L SUM | 1 | 1 | | XZ0029654 | HIGH TENSION CABLE MEDIAN BARRIER TERMINALS | EACH | 10 | 10 | | | |
| X4060995 | TEMPORARY RAMP, SPECIAL | SQ YD | 100 | | 100 | Z0029999 | IMPACT ATTENUATOR REMOVAL | EACH | 2 | 2 | | | |
| X4400600 | ENDS SECTIONS TO BE REMOVED | EACH | 2 | 2 | | Z0030250 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 2 | | 2 | | |
| X4402020 | CONCRETE MEDIAN SURFACE REMOVAL | SQ FT | 891 | 891 | | XZ0030270 | IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, WIDE), TEST LEVEL 3 | EACH | 8 | | 8 | | |
| X4421000 | PARTIAL DEPTH PATCHING | TON | 1813 | 1813 | | XZ0030330 | IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3 | EACH | 4 | | 4 | | |
| X5010522 | REMOVE CONCRETE END SECTION | EACH | 3 | 3 | | Z0030350 | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 2 | | 2 | | |
| X6350120 | DELINEATOR REMOVAL | EACH | 248 | 248 | | Z0032470 | JOINT SEALER | FOOT | 442 | | 442 | | |
| X7010216 | TRAFFIC CONTROL AND PROTECTION, (SPECIAL) | L SUM | 1 | | 1 | Z0038115 | PORTLAND CEMENT CONCRETE SURFACE REMOVAL 1/2" | SQ YD | 113791 | 113791 | | | |
| X7330070 | OVERHEAD SIGN SUPPORT GROUT REPAIR | EACH | 5 | 5 | | Z0041895 | POLYMER CONCRETE | CU FT | 25 | | 25 | | |
| X7330112 | SAFETY CHAIN | EACH | 8 | 8 | | Z0048665 | RAILROAD PROTECTIVE LIABILITY INSURANCE | L SUM | 1 | | 1 | | |
| X7333095 | OVERHEAD SIGN STRUCTURE - SPAN, (SPECIAL) | FOOT | 67.5 | 67.5 | | + Z0076600 | TRAINEES | HOUR | 3,000 | 3,000 | | | |
| X7830070 | GROOVING FOR RECESSED PAVEMENT MARKING 5" | FOOT | 2096 | 2096 | | X7330094 | INTERNAL TRUSS DAMPER | EACH | 1 | 1 | | | |
| X7830076 | GROOVING FOR RECESSED PAVEMENT MARKING 9" | FOOT | 580 | 580 | | X7330090 | METAL SCREEN | EACH | 1 | 1 | | | |
| X8360120 | LIGHT POLE FOUNDATION, SPECIAL | EACH | 12 | 12 | | X7360106 | REMOVE OVERHEAD SIGN STRUCTURE-SPAN, SPECIAL | EACH | 1 | 1 | | | |
| X8440110 | RELOCATE EXISTING LIGHT POLE WITH LUMINAIRE | EACH | 12 | 12 | | 40603243 | POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90 | TON | 14121 | 14121 | | | |
| Z0001899 | JACK AND REMOVE EXISTING BEARINGS | EACH | 156 | | 156 | | | | | | | | |
| Z0001903 | STRUCTURAL STEEL REMOVAL | POUNDS | 1280 | | 1280 | | | | | | | | |
| Z0004556 | HOT-MIX ASPHALT SURFACE REMOVAL (DECK) | SQ YD | 6954 | 6954 | | | | | | | | | |
| Z0005300 | BOX CULVERTS TO BE CLEANED | EACH | 1 | | 1 | | | | | | | | |
| Z0007101 | CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1 | L SUM | 1 | | 1 | | | | | | | | |
| Z0007102 | CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 2 | L SUM | 1 | | 1 | | | | | | | | |
| Z0010400 | CLEANING BRIDGE SEATS | SQ FT | 2769 | | 2769 | | | | | | | | |
| Z0010605 | CLEANING DRAINAGE SYSTEM | L SUM | 1 | | 1 | | | | | | | | |
| Z0010615 | CLEANING EXISTING INLETS | EACH | 6 | | 6 | | | | | | | | |