

SURFACE REMOVAL BUTT- JOINT				
LOCATION			PCC SURFACE REMOVAL BUTT-JOINT	HMA SURFACE REMOVAL BUTT-JOINT
STA.	TO	STA.	(SQ YD)	(SQ YD)
I-64 EASTBOUND				
243+50	TO	244+71		887
247+26	TO	248+26		889
263+73	TO	264+73		1211
265+83	TO	266+83		1156
336+00	TO	337+00		856
I-64 WESTBOUND				
243+50	TO	245+32		1335
247+77	TO	248+97		893
263+53	TO	264+53		1111
265+67	TO	266+67		1156
303+75	TO	304+75	678	300
306+00	TO	307+00	656	322
336+00	TO	337+00		833
RAMP C				
4+55	TO	5+55	178	67
6+71	TO	7+71	178	67
RAMP D				
11+65	TO	12+65	178	111
RAMP G				
1+71	TO	2+71	178	111
RAMP H				
25+18	TO	26+18	178	111
IL 157 EXIT RAMP				
336+00	TO	337+00	178	111
RAMP A				
17+15	TO	18+15	178	111
RAMP B				
1+73	TO	2+73	178	111
RAMP F				
9+35	TO	10+35	178	111
RAMP E				
2+00	TO	3+00	178	111
IL 157 ENTRANCE RAMP				
336+00	TO	337+00	178	111
TOTAL:			3292	12082

NOTE: BUTT - JOINTS AT BRIDGES SHALL INCLUDE THE REMOVAL OF ALL EXISTING HMA PATCHING.

DRAINAGE MISCELLANEOUS ITEMS										
LOCATION	RT/LT	CLEAN EXISTING INLET	CLEAN EXISTING END SECTION	BOX CULVERT TO BE CLEANED	REMOVE CONCRETE END SECTIONS	END SECTIONS TO BE REMOVED	PRC FLARED END SECTION 24"	PRC FLARED END SECTION 36"	END SECTION 24"	INSERTION CULVERT LINER, 24"
STA		(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(FOOT)
244+35	RT	1								
245+00	MEDIAN	1								
247+20	MEDIAN	1								
247+78	MEDIAN	1								
255+00	MEDIAN	1								
255+02	RT					1			1	187
261+31	RT					1			1	92
292+27	RT				1		1			
299+47	LT		1							
299+73	LT				1		1	1		
299+75	MEDIAN	1								
310+00	RT		1							
320+00	RT				1					
334+42	RT			1						
TOTAL:		6	2	1	3	2	2	1	2	279

NOTE: IT IS THE CONTRACTORS RESPONSIBILITY TO MAKE SURE THE APPROPRIATE SIZE LINER WILL FIT INTO THE PIPE CULVERT.

HIGH TENSION CABLE MEDIAN BARRIER				
LOCATION			HIGH TENSION CABLE MEDIAN BARRIER	HIGH TENSION CABLE MEDIAN BARRIER TERMINALS
STA	TO	STA	(FOOT)	(EACH)
I-64 EB - LT				
248+18.25	TO	248+68.25		1
248+68.25	TO	259+95.25	1127	
259+95.25	TO	260+45.25		1
265+78.00	TO	266+28.00		1
266+28.00	TO	279+50.00	1322	
279+50.00	TO	280+00.00		1
I-64 WB - RT				
279+56	TO	280+06		1
280+06.00	TO	304+12.00	2406	
304+12.00	TO	304+62.00		1
306+17.50	TO	306+67.50		1
306+67.50	TO	317+40.00	1073	
317+40.00	TO	317+90.00		1
320+62.50	TO	321+12.50		1
321+12.50	TO	330+70.00	958	
330+70.00	TO	331+20.00		1
TOTAL:			6885	10

REMOVE HIGH TENSION CABLE MEDIAN BARRIER				
LOCATION			CABLE MEDIAN REMOVAL	
STA	TO	STA	(FOOT)	
I-64 EB - LT				
248+50	TO	261+20	1270	
265+78	TO	280+00	1422	
I-64 WB - RT				
279+56	TO	304+62	2506	
306+18	TO	331+50	2533	
TOTAL:			7731	