

BILL OF MATERIALS

BILL OF MATERIALS			TOTAL
CODE NO	ITEM	UNIT	QUANTITIES
	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1
	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1
	SIGN PANEL - TYPE 3	SQ FT	2836
	REMOVE SIGN PANEL - TYPE 3	SQ FT	3162
	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (SPECIAL)	FOOT	67.5
	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	36
	REMOVE AND REERECT OVERHEAD SIGN STRUCTURE-SPAN	EACH	1
	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	8
	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	5
	FURNISH AND INSTALL INTERNAL TRUSS DAMPER	EACH	1
	FURNISH AND INSTALL SAFETY CHAIN	EACH	8
	FURNISH AND INSTALL METAL SCREEN	EACH	1
	REMOVE OVERHEAD SIGN STRUCTURE-SPAN, SPECIAL	EACH	1

SIGN PANEL REMOVAL						
STATION	STRUCTURE #	F&I SAFETY CHAIN	REMOVAL OF LIGHTING UNIT, SALVAGE	F&I METAL SCREEN	OVERHEAD SIGN SUPPORT GROUT REPAIR	REMOVAL SIGN PANEL TYPE 3
		(EACH)	(EACH)	(EACH)	(EACH)	(SQ FT)
248+03	8S082I064R006.5	1	1			728
249+90	8C082I064L006.5		1			219
262+36	8S082I064R006.7	1			4	
278+75	8C082I064R006.9	1	1	1		136
280+16	8B082I064R007.0	1	1			154
284+79	8C082I064L006.9	1	1		1	196
305+36	8B082I064L007.4	1	1			384
316+35	8C082I064R007.9					225
318+01	8S082I064L008.0	1	1			768
333+00	8C082I064R008.3	1	1			352
TOTAL =		8	8	1	5	3162

SIGN STRUCTURES					
STATION	STRUCTURE #	REMOVE OVERHEAD SIGN STRUCTURE - SPAN, SPECIAL	OVERHEAD SIGN STRUCTURE-SPAN, TYPE 1-A (SPECIAL)	OVERHEAD SIGN STRUCTURE WALKWAY TYPE A (FOOT)	F&I INTERNAL TRUSS DAMPER (EACH)
262+36	8S082I064R006.7	1	67.5	36	1
TOTAL :		1	67.5	36	1

SIGN PANELS			
LOCATION	STRUCTURE #	SIGN PANEL #	SIGN PANEL TYPE 3
STA.			(SQ FT)
248+03	8S082I064R006.5	SP7-1	283.5
		SP7-2	200
249+90	8C082I064L006.5	SP17-1	286
262+36	8S082I064R006.7	SP8-1	130
		SP8-2	180
278+75	8C082I064R006.9	SP9-1	132
280+16	8B082I064R007.0	SP10-1	175
284+79	8C082I064L006.9	SP16-1	175
305+36	8B082I064L007.4	SP15-1	187.5
		SP15-2	140
316+35	8C082I064R007.9	SP12-1	182
318+01	8S082I064L008.0	SP14-1	283.5
		SP14-2	262.5
333+00	8C082I064R008.3	SP13-1	218.75
TOTAL =			2836

FILE NAME =	USER NAME = burnsideem	DESIGNED -	REVISED -
c:\pwork\pwork\burnsideem\d0109244\0876415-sht-plan.dgn		DRAWN -	REVISED -
PLOT SCALE = 50.0000' / 1" =		CHECKED -	REVISED -
PLOT DATE = 11/21/2011		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BILL OF MATERIALS /SCHEDULE

SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-(3,4)RS	ST. CLAIR	167	68
FED. ROAD DIST. NO. - [ILLINOIS] FED. AID PROJECT				
CONTRACT NO. 76415				