



PARTIAL PLAN SHOWING CONCRETE REPLACEMENT



MIN. BAR LAP
#5 - 2'-11"

NOTES:

- 1.) *Existing reinforcement extending into the removal area shall be cleaned, straightened and incorporated into the new construction. Any reinforcement bars that are damaged during concrete removal shall be replaced with an approved bar splicer or anchorage system. Cost shall be included with Concrete Removal.
- 2.) For Section B-B, see Sheet B15.
- 3.) For Bill of Material, see Sheet B15.
- 4.) E.E. denotes Each End, I.F. denotes Inside Face and O.F. denotes Outside Face.

Farnsworth
GROUP, INC.
2709 McGraw Drive
Bloomington, Illinois 61704
309/663-8436, 309/663-1571 fax

DESIGNED - JCZ	REVISED
CHECKED - JML	REVISED
DRAWN - DJM/JWK	REVISED
DATE - 12/05/11	REVISED
CHECKED - MSW	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

EXPANSION JOINT REPLACEMENT DETAILS, WESTBOUND ROADWAY
STRUCTURE NO. 082-0169 (E.B.)
STRUCTURE NO. 082-0170 (W.B.)

SHEET NO. B14 OF 34 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-13,41RS	ST. CLAIR	167	135
CONTRACT NO. 76415				
ILLINOIS FED. AID PROJECT				