

TOTAL BILL OF MATERIAL

ITEMS	UNITS	SUPER	SUB	TOTAL
Stone Riprap, Class A3	Sq. Yd.		6	6
Hot-Mix Asphalt Surface Course, Mix "C", N70	Ton	133		133
Protective Shield	Sq. Yd.	360		360
Protective Coat	Sq. Yd.	262		262
Waterproofing Membrane System	Sq. Yd.	1,191		1,191
Remove Overhead Sign Structure - Bridge Mounted	Each	1		1
Structural Repair of Concrete (Depth Equal to or Less than 5 Inches)	Sq. Ft.		115	115
Silicone Joint Sealer, 2"	Foot	84		84
Joint Sealer	Foot	108		108
Polymer Concrete	Cu. Ft.	25		25
Polymer Modified Portland Cement Mortar	Sq. Ft.	14		14
Slope Wall Crack Sealing	Foot		48	48
Temporary Ramp, Special	Sq. Yd.	35		35

GENERAL NOTES

- 1.) Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.
- 2.) Protective coat shall not be applied to surfaces to which Waterproofing Membrane System is applied.
- 3.) All areas of erosion are to be repaired by placing Class A3 Stone Riprap in a manner to match the existing ground profile or to improve the ground profile.
- 4.) The area along the Slope walls as determined by the Engineer should be cleared of vegetation, brush, saplings, etc. according to Section 201 of the Standard Specification. This work shall be included with Stone Riprap, Class A3.
- 5.) Joint openings shall be adjusted according to Article 520.04 of the Standard Specifications when the expansion joint's bent \bar{E} is installed at an ambient temperature other than 50°F.
- 6.) The hot-mix asphalt mixture requirements are included in the roadway plans.



DESIGNED - JCZ	REVISED
CHECKED - JML	REVISED
DRAWN - DJM/JWK	REVISED
CHECKED - MSW	REVISED
DATE - 11/17/11	

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**GENERAL DATA
STRUCTURE NO. 082-0261**

SHEET NO. C2 OF 10 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-(3,4)RS	ST. CLAIR	167	157
CONTRACT NO. 76415				
ILLINOIS FED. AID PROJECT				