SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	100% STATE URBAN TOTAL QUANTITY	ST. CLAIR COUNTY ROADWAY	BRIDGE	LIGHTING	ITS					
				CONSTRUCTION TYPE CODE 0001	0008	0021	0021					
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	158	158								
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	34	34								
20100500	TREE REMOVAL, ACRES	ACRE	7.75	7.75								
20101000	TEMPORARY FENCE	FOOT	157	157								
20200100	EARTH EXCAVATION	CU YD	44,805	44,805								
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	20,449	20449								
20400800	FURNISHED EXCAVATION	CU YD	71,855	71,855								
20800150	TRENCH BACKFILL	CU YD	852	852								
21301060	EXPLORATION TRENCH 60" DEPTH	FOOT	100	100								
21301084	EXPLORATION TRENCH 84" DEPTH	FOOT	100	100								
25100115	MULCH, METHOD 2	ACRE	17.5	17.5								
25100630	EROSION CONTROL BLANKET	SQ YD	35,680	35,680								
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	9,900	9,900								
28000305	TEMPORARY DITCH CHECKS	FOOT	338	338								
28000400	PERIMETER EROSION BARRIER	FOOT	11,135	11,135								
28000500	INLET AND PIPE PROTECTION	EACH	19	19								
28000510	INLET FILTERS	EACH	27	27								
28100105	STONE RIPRAP, CLASS A3	SQ YD	98	98								
28100109	STONE RIPRAP, CLASS A5	SQ YD	52	52								
28200200	FILTER FABRIC	SQ YD	52	52								
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	30,247	30,247								
35101400	AGGREGATE BASE COURSE, TYPE B	TON	11	11								
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	1,333	1,333								
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	2,174	2,174								
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	245	245								
40600300	AGGREGATE (PRIME COAT)	TON	5	5								
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	456	456								
40701996	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 15 3/4"	SQ YD	566	566								
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	18,509	18,509								
42000521	PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED)	SQ YD	7,467	7,467								

* DENOTES SPECIALTY ITEMS

● 0042

..\DBCONN-11-BORDER1.DGN, ..\DBCONN-11-SOG1.DGN, ..\DBCONN-99-MOTIF1.DGN, ..\DBCONN-11-LEGEND1.DGN, ..\DBCONN-11-MOTIF1.DGN
10-19-2011, 14:53:32 BONDHUJD \\FS-0044\AM\VAULT\D-TRANS.07\2202\20868-001\CIVIL\CAD\99 ALL CONTRACTS\CONN\SHEETS CONTRACT 11\DBCONN-11-SHT-SUMMARY1.DGN

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED - JB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES 1	F.A.P. RTE. 998	SECTION 82-2-1K	COUNTY ST. CLAIR	TOTAL SHEETS 353 / SHEET NO. 4
TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS	PLOT SCALE = $SCALE$	DRAWN - JB	REVISED -	PROPOSED RELOCATED IL ROUTE 3 INTERCHANGE				CONTRACT NO. 76E06	
	PLOT DATE = $DATE$	CHECKED - ACL	REVISED -		SCALE: N.T.S. / SHEET NO. 1 OF 9 SHEETS / STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	
		DATE - 10/21/11	REVISED -						