SUMMARY OF QUANTITIES

			100% STATE URBAN	ST. CLAIR COUNTY								
				ROADWAY	BRIDGE	LIGHTING	ITS					
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE								
				0001	0008	0021	0021					
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	4	4								
60204805	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	1	1								
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1								
60240310	INLETS, TYPE B, TYPE 11 FRAME AND GRATE	EACH	6	6								
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	5	5								
60255500	MANHOLES TO BE ADJUSTED	EACH	12	12								
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1								
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	16	16								
60402210	GRATES, TYPE 8	EACH	4	4								
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	1								
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	7.4	7.4								
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	901	901								
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1,214	1,214								
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	34	34								
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	255	255								
60618320	CONCRETE MEDIAN SURFACE, 6 INCH	SQ FT	12,130	12,130								
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	5,211	5,211								
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	1,912	1,912								
60623200	CONCRETE MEDIAN, TYPE SM-6.24	SQ FT	119	119								
✱ 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	700	700								
✱ 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2								
✱ 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2	2								
✱ 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2								
✱ 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2								
63500105	DELINEATORS	EACH	83	83								
66400305	CHAIN LINK FENCE, 6'	FOOT	5,044	5,044								
66408000	CHAIN LINK GATES, 6' X 20' DOUBLE	EACH	2	2								
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	36	36								
✱ 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	10,000	10,000								
✱ 66900400	SPECIAL WASTE GROUNDWATER DISPOSAL	GALLON	5,000	5,000								

✱ DENOTES SPECIALTY ITEMS

● 0042

..\DBCONN-11-BDRUERLIGN..\DBCONN-11-SDGLIGN..\DBCONN-99-MOTIF1.DGN..\DBCONN-11-LEGENDLIGN..\DBCONN-11-MOTIF1.DGN
10-19-2011, 14:54:20 BDNDHUD \\FS-0044\AM\VAULT_D-TRANS_07\2282\206868-00\CIVIL\CADD\99 ALL CONTRACTS\CONN SHEETS CONTRACT 11\DBC

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED - JB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES 4
TENG TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS		DRAWN - JB	REVISED -	PROPOSED RELOCATED IL ROUTE 3 INTERCHANGE	
	PLOT SCALE = $SCALE$	CHECKED - ACL	REVISED -		SCALE: N.T.S. SHEET NO. 4 OF 9 SHEETS STA. TO STA.
	PLOT DATE = $DATE$	DATE - 10/21/11	REVISED -		

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
998	82-2-1K	ST. CLAIR	353	7
		CONTRACT NO. 76E06		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		