SUMMARY OF QUANTITIES

	CODE NO.	ITEM	UNIT	100% STATE URBAN TOTAL QUANTITY	ST. CLAIR COUNTY ROADWAY CONSTRUCTION TYPE CODE 0001	BRIDGE 0008	LIGHTING 0021	ITS 0021					
*	78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	6,732	6,732								
*	78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"	FOOT	242	242								
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	175	175								
*	78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4	4								
*	78200300	PRISMATIC CURB REFLECTOR	EACH	187	187								
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16								
*	78200520	BARRIER WALL MARKERS, TYPE B	EACH	10	10								
*	78200530	BARRIER WALL MARKERS, TYPE C	EACH	27	27								
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4								
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,288	2,288								
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	31	31								
*	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1			1						
*	80500100	SERVICE INSTALLATION, TYPE A	EACH	4				4					
*	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	347			347						
*	81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	243				243					
*	81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	5,874				5,874					
*	81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	~~6~~				6					
*	81200250	CONDUIT EMBEDDED IN STRUCTURE, 3" DIA., PVC	FOOT	30				30					
*	81200270	CONDUIT EMBEDDED IN STRUCTURE, 4" DIA., PVC	FOOT	15				15					
*	81300835	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" X 18" X 10"	EACH	4				4					
*	81300915	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 20" X 20" X 8"	EACH	3				3					
	~~81300980~~	~~JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 8" X 8" X 6"~~	~~EACH~~	~~2~~			~~2~~						
*	81400100	HANDHOLE	EACH	10				10					
*	81400300	DOUBLE HANDHOLE	EACH	7				7					
*	~~81702110~~	~~ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10~~	~~FOOT~~	~~2,760~~			~~2,760~~						
*	81702415	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 6	FOOT	1,789			1,789						
*	82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	23			23						
*	82500340	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 480VOLT, 60AMP	EACH	1			1						
*	83009600	LIGHT POLE, ALUMINUM, 45 FT. M.H., 15 FT. MAST ARM	EACH	23			23						
*	~~83060800~~	LIGHT POLE, GALVANIZED STEEL, 30 FT. M.H., TENON MOUNT	EACH	1				1					

* DENOTES SPECIALTY ITEMS

● 0042

..\DBCONN-11-BORDER.DGN ..\DBCONN-11-SGD.DGN ..\DBCONN-99-MOTIF.DGN ..\DBCONN-11-LEGEND.DGN ..\DBCONN-11-MOTIF.DGN
10/19/2011 14:54:46 BONDHUD \\FS-0044\VAV\VAULT\D-TRANS_07\2202\28868-00I\CIVIL\CAD\99 ALL CONTRACTS\DGNS\SHEETS CONTRACT II\DBCONN-11-SHT-SUMMARY6.DGN

FILE NAME = $FILE$	USER NAME = $USER$	DESIGNED - JB	REVISED -	
TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS		DRAWN - JB	REVISED -	
	PLOT SCALE = $SCALE$	CHECKED - ACL	REVISED -	
	PLOT DATE = $DATE$	DATE - 10/21/11	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
PROPOSED RELOCATED IL ROUTE 3 INTERCHANGE

SUMMARY OF QUANTITIES 6

SCALE: N.T.S. | SHEET NO. 6 OF 9 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
998	82-2-1K	ST. CLAIR	353	9
		CONTRACT NO. 76E06		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		