SUMMARY OF QUANTITIES

	CODE NO.	ITEM	UNIT	100% STATE URBAN TOTAL QUANTITY	ST. CLAIR COUNTY ROADWAY CONSTRUCTION TYPE CODE 0001	BRIDGE 0008	LIGHTING 0021	ITS 0021					
*	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	5				5					
*	83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	124			117	7					
*	83700300	LIGHT TOWER FOUNDATION, 48" DIAMETER	FOOT	33				33					
*	83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	18			18						
*	X8630103	CONTROLLER CABINET TYPE III, SPECIAL	EACH	3				3					
*	87100110	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 6F	FOOT	4,396				4,396					
*	87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	13,007				13,007					
*	87800210	CONCRETE FOUNDATION, TYPE D (SPECIAL)	FOOT	11				11					
*	87900200	DRILL EXISTING HANDHOLE	EACH	1				1					
*	X0322227	CLOSED CIRCUIT TELEVISION CAMERA SYSTEM	EACH	3				3					
	X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	5	5								
	X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	550	550								
	X0324993	SEPARATION JOINT WITH SLEEPER SLAB	FOOT	676	676								
*	X0325076	WIDE AREA NETWORK	L SUM	1				1					
*	X0325077	FIBER OPTIC UTILITY MARKER	EACH	20				20					
	X0325155	REMOVE ABANDONED GAS MAIN	FOOT	300	300								
*	X0325476	RADAR VEHICLE DETECTION SYSTEM	EACH	2				2					
*	X0325482	REMOVE EXISTING ITS EQUIPMENT	EACH	1				1					
*	X0325483	SFP-GE-L SFP MODULE	EACH	5				5					
*	X0325485	TRUSS MOUNTED LED DYNAMIC MESSAGE SIGN	EACH	1				1					
*	X0325487	WIRED COMMUNICATION DATA CONVERTOR	EACH	3				3					
*	X0325593	LIGHT TOWER, 80 FT. WITH CAMERA LOWERING SYSTEM	EACH	2				2					
*	X0326091	LIGHT POLE, STEEL 50 FT. WITH CAMERA LOWERING SYSTEM	EACH	1				1					
*	X0326802	UTILITY STRUCTURE REMOVAL	EACH	31	31								
*	X0326912	3000 LAYER 2 SWITCH	EACH	2				2					
*	X0327096	ETHERNET MODEM	EACH	4				4					
	X2010505	CLEARING, SPECIAL	L SUM	1	1								
	X2020410	EARTH EXCAVATION (SPECIAL)	CU YD	2,135	2,135								
	X4020700	AGGREGATE SURFACE COURSE, TYPE B 8"	SQ YD	160	160								
	X5012502	CONCRETE REMOVAL (SPECIAL)	CU YD	50	50								

* DENOTES SPECIALTY ITEMS

● 0042

\\DBCONN-11-BORDERLDGN, \\DBCONN-11-SQQ1.DGN, \\DBCONN-99-MOTIF.LDGN, \\DBCONN-11-LEGEND1.DGN, \\DBCONN-11-MOTIF.LDGN
10-19-2011, 14:54:59 BOND#4J0 \\VFS-0044\AMVVAULT\D-TRANS_07\2202\28868-001\CIVIL\CAD\99 ALL CONTRACTS\CONN SHEETS CONTRACT 11\DBCONN-11-SUMMARY7.DGN

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED - JB	REVISED -	**STATE OF ILLINOIS**
TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS		DRAWN - JB	REVISED -	**DEPARTMENT OF TRANSPORTATION**
	PLOT SCALE = $SCALE$	CHECKED - ACL	REVISED -	PROPOSED RELOCATED IL ROUTE 3 INTERCHANGE
	PLOT DATE = $DATE$	DATE - 10/21/11	REVISED -	

SUMMARY OF QUANTITIES 7

SCALE: N.T.S. | SHEET NO. 7 OF 9 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
998	82-2-1K	ST. CLAIR	353	10
		CONTRACT NO. 76E06		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		