STONE RIPRAP, CLASS A3 — TOTAL 98 SQ YD

LOCATION	STATION	OFF.	TO OFF.	AREA SQ FT	SUBTOTALS
PR. REL. IL RTE 3	1668+38.50	91.6 LT	101.1 LT	73	8
PR. REL. IL RTE 3	1671+56.00	115.5 LT	130.8 LT	210	23
PR. REL. IL RTE 3	1671+80.00	119.0 LT	128.9 LT	73	8
PR. REL. IL RTE 3	1691+50.00	44.9 RT	53.4 RT	62	7
CONNECTOR	23+30.00	60.7 RT	70.7 RT	93	10
CONNECTOR	27+50.00	49.6 RT	59.6 RT	93	10
CONNECTOR	31+50.00	49.6 RT	65.5 RT	181	20
EXCHANGE	39+33.00	55.7 RT	65.5 RT	101	11

FILTER FABRIC — TOTAL 52 SQ YD

STONE RIPRAP, CLASS A5 — TOTAL 52 SQ YD

LOCATION	STATION	OFFSET	OFFSET	AREA SQ FT	SUBTOTALS
CONNECTOR	23+00.00	84.8 LT	105 LT	468	52
CONNECTOR	23+00.00	84.7 LT	105.0 LT	468	52

STABILIZED SUBBASE - HOT-MIX ASPHALT, 4" — TOTAL 30,247 SQ YD

LOCATION	STATION	STATION	AREA SQ FT	SUBTOTALS
RAMP C	110+68.51	116+40.00	11,042	1,227
RAMP C	110+68.51	110+39.97	541	60
RAMP C	116+40.00	120+30.22	11,249	1,250
RAMP D	250+22.64	254+00.00	13,418	1,491
RAMP D	258+00.00	254+00.00	9,439	1,049
EXCHANGE	35+11.34	43+00.00	36,276	4,031
EXCHANGE	43+00.00	52+53.99	51,350	5,706
CONNECTOR	20+47.00	22+50.00	11,105	1,234
CONNECTOR	22+50.00	32+40.65	36,594	4,066
WT DRIVE	900+50.00	902+99.68	6,001	667
PR. REL. IL RTE 3	1668+15.65	1676+87.75	47,499	5,278
PR. REL. IL RTE 3	1684+69.18	1687+40.00	10,398	1,155
PR. REL. IL RTE 3	1687+40.00	1692+96.82	27,313	3,035

AGGREGATE BASE COURSE, TYPE B — TOTAL 11 TON

LOCATION	STATION	STATION	AREA (SF)	THICKNESS (IN)	TONS/CY	SUBTOTALS
RAMP C	120+06.74	120+19.28	136	14	1.8	10.58

AGGREGATE BASE COURSE, TYPE B 6" — TOTAL 1,333 SQ YD

LOCATION	STATION	STATION	AREA (SQ FT)	SUBTOTALS
RAMP C	119+85.13	120+13.28	775	86.1
PR. REL. IL RTE 3	1671+39.76	1676+87.75	6,937	770.8
	1685+27.51	1687+40.00	1,952	216.9
	1687+40.00	1689+77.98	2,330	258.9

BITUMINOUS MATERIALS (PRIME COAT) — TOTAL 245 GALLON

DESCRIPTION	AREA SQ YD	SUBTOTALS
RESURFACING ON EX. ST. CLAIR - ITEM 40603340	4,074	204
PAVEMENT WIDENING ON EX. ST. CLAIR - ITEM 40701996	566	28
TEMPORARY PAVEMENT ON EXCHANGE - ITEM Z0062456	253	13

APPLICATION RATE 0.05 GAL/SQ YD

AGGREGATE (PRIME COAT) — TOTAL 5 TON

DESCRIPTION	AREA SQ YD	SUBTOTALS
RESURFACING ON EX. ST. CLAIR - ITEM 40603340	4,074	4.1
PAVEMENT WIDENING ON EX. ST. CLAIR - ITEM 40701996	566	0.6
TEMPORARY PAVEMENT ON EXCHANGE - ITEM Z0062456	253	0.3

APPLICATION RATE 2 LBS/SQ YD

HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 — TOTAL 456 TON

LOCATION	STA	STA	LT / RT	AREA SQ FT	THICKNESS IN.	SUBTOTALS
EX. ST. CLAIR	107+15.07	109+00.00	LT & RT	5,510	2	69
EX. ST. CLAIR	109+00.00	117+00.00	LT & RT	23,357	2	291
EX. ST. CLAIR	117+00.00	119+42.50	LT & RT	7,124	2	89
EX. ST. CLAIR	118+49.80		LT	675	2	8

HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 15 3/4" — TOTAL 566 SQ YD

LOCATION	STATION	STATION	LT / RT	AREA SQ FT	SUBTOTALS
EX. ST. CLAIR	108+47.72	109+00.00	RT	45	5
EX. ST. CLAIR	109+00.00	117+00.00	RT	4,805	534
EX. ST. CLAIR	117+00.00	118+31.65	RT	243	27

PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED) — TOTAL 18,509 SQ YD

LOCATION	STATION	STATION	AREA SQ FT	SUBTOTALS
RAMP C	110+40.00	110+68.46	456	51
RAMP C	110+68.46	116+40.00	9,298	1,033
RAMP C	116+40.00	120+29.95	9,370	1,041
RAMP D	254+00.00	250+22.40	11,980	1,331
RAMP D	258+00.00	254+00.00	8,213	913
EXCHANGE	35+11.34	43+00.00	31,883	3,543
EXCHANGE	43+00.00	52+52.49	46,201	5,133
CONNECTOR	20+47.00	22+50.00	10,427	1,159
CONNECTOR	22+50.00	32+40.64	33,429	3,714
WT DRIVE	900+50.00	903+01.13	5,328	592

PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED) — TOTAL 7,467 SQ YD

LOCATION	STATION	STATION	OFFSET	AREA SQ FT	SUBTOTALS
PR. REL. IL RTE 3	1668+15.65	1675+87.75		37,491	4,166
PR. REL. IL RTE 3	1685+70.43	1687+40.00	LT	2,775	308
PR. REL. IL RTE 3	1685+70.43	1687+40.00	RT	2,035	226
PR. REL. IL RTE 3	1687+40.00	1693+05.42		24,906	2,767

PORTLAND CEMENT CONCRETE PAVEMENT 12" (JOINTED) — TOTAL 651 SQ YD

LOCATION	STATION	STATION	LT / RT	AREA SQ FT	SUBTOTALS
EXCHANGE	52+52.49	54+74.68	RT	2,872	319
EXCHANGE	52+52.49	54+77.20	LT	2,985	332

.\DBCONN-11-BORDER1.DGN -.\DBCONN-11-SCHEDDU.DGN -.\DBCONN-11-SCHEDDU.DGN -.\DBCONN-99-MOTIF1.DGN -.\DBCONN-11-MOTIF1.DGN
10-19-2011, 14:58:27 BONDHALD \\FS-0044\JAMS\HALD-HANKS.87\22222\20059-000\CIVIL\CADD\99 ALL CONTRACTS\DGNS\SHEETS CONTRACT 11\DBCONN-11-SHT-SCHEDULE4.JDGN