



MATCH LINE STA. 43+00
SEE SHEET 97

EROSION CONTROL LEGEND

- INLET FILTERS/INLET & PIPE PROTECTION
- PERIMETER EROSION BARRIER (PEB)
- TEMPORARY EROSION CONTROL SEEDING/
EROSION CONTROL BLANKET
- TEMPORARY DITCH CHECK
- TEMPORARY EROSION CONTROL SEEDING/
MULCH, METHOD 2
- STABILIZED CONSTRUCTION ENTRANCE

GENERAL NOTE:

1. ONCE TEMPORARY EROSION CONTROL IS PLACED FOR A STAGE IT SHALL REMAIN IN PLACE UNTIL COMPLETION OF CONSTRUCTION OR UNTIL PERMANENT LANDSCAPING MEASURES ARE INSTALLED (BY OTHERS). INLET FILTERS SHALL REMAIN IN PLACE UNTIL PERMANENT LANDSCAPING ITEMS ARE INSTALLED.



USER NAME = Plotted by Scott Wilkinson	DESIGNED - AS	REVISED -
	DRAWN - AS	REVISED -
PLOT SCALE = 50.0000' / 1 in.	CHECKED - ST	REVISED -
PLOT DATE = 10/17/2011	DATE - 10/21/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**
PROPOSED RELOCATED ILLINOIS ROUTE 3 INTERCHANGE

**PR. EXCHANGE AVE., RAMPS C AND D
EROSION CONTROL PLANS - STAGE 1
STA. 35+00 TO STA. 43+00**

SCALE: 1"=50' SHEET NO. 1 OF 13 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
998	82-2-1K	ST. CLAIR	353	96
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 76E06	