PR. ST. CLAIR CONNECTOR

STATION	LEFT EDGE OF SHOULDER	LEFT SHOULDER SLOPE	LEFT EDGE OF PAVEMENT	LEFT EOP TO PGL SLOPE	LEFT EOP TO PGL WIDTH (FT)	PGL	RIGHT EOP TO PGL WIDTH (FT)	RIGHT EOP TO PGL SLOPE	RIGHT EDGE OF PAVEMENT	RIGHT SHOULDER SLOPE	RIGHT EDGOE OF SHOULDER	COMMENTS
21+40.00	417.03	4.00%	417.19	-1.50%	24.00	417.55	16.19	1.50%	417.31	4.00%	417.15	NORMAL CROWN
21+50.00	416.95	4.00%	417.11	-1.00%	24.00	417.35	15.08	1.50%	417.12	4.00%	416.96	
21+70.00	416.79	4.00%	416.95	0.00%	24.00	416.95	14.03	1.50%	416.74	4.00%	416.58	0% IN ONE LANE
21+73.64	416.76	4.00%	416.92	0.18%	24.00	416.88	14.00	1.50%	416.67	4.00%	416.51	
21+75.00	416.75	4.00%	416.91	0.25%	24.00	416.85	14.00	1.50%	416.64	4.00%	416.48	
22+00.00	416.54	4.00%	416.70	1.50%	23.23	416.35	13.71	1.50%	416.14	4.00%	415.98	1.5% SE
22+13.40	416.41	4.00%	416.57	2.20%	22.19	416.08	13.33	2.20%	415.79	4.00%	415.63	PC
22+25.00	416.28	4.00%	416.44	2.79%	21.26	415.85	13.00	2.79%	415.49	4.00%	415.33	
22+45.00	416.04	4.00%	416.20	3.80%	19.67	415.45	12.43	3.80%	414.98	4.00%	414.82	FULL S.E.
22+50.00	415.93	4.00%	416.09	3.80%	19.28	415.35	12.29	3.80%	414.89	4.00%	414.73	
22+75.00	415.41	4.00%	415.57	3.80%	17.32	414.91	12.00	3.80%	414.45	4.00%	414.29	
23+00.00	414.94	4.00%	415.10	3.80%	15.39	414.52	12.00	3.80%	414.06	4.00%	413.90	
23+25.00	414.54	4.00%	414.70	3.80%	13.49	414.19	12.00	3.80%	413.73	4.00%	413.57	
23+45.00	414.26	4.00%	414.42	3.80%	12.00	413.96	12.00	3.80%	413.51	4.00%	413.35	
23+50.00	414.21	4.00%	414.37	3.80%	12.00	413.91	12.00	3.80%	413.46	4.00%	413.30	
23+75.00	413.99	4.00%	414.15	3.80%	12.00	413.70	12.00	3.80%	413.24	4.00%	413.08	
24+00.00	413.84	4.00%	414.00	3.80%	12.00	413.54	12.00	3.80%	413.08	4.00%	412.92	
24+25.00	413.71	4.00%	413.87	3.80%	12.00	413.41	12.00	3.80%	412.96	4.00%	412.80	
24+50.00	413.58	4.00%	413.74	3.80%	12.00	413.28	12.00	3.80%	412.83	4.00%	412.67	
24+75.00	413.45	4.00%	413.61	3.80%	12.00	413.16	12.00	3.80%	412.70	4.00%	412.54	
25+00.00	413.33	4.00%	413.49	3.80%	12.00	413.03	12.00	3.80%	412.57	4.00%	412.41	
25+25.00	413.20	4.00%	413.36	3.80%	12.00	412.90	12.00	3.80%	412.45	4.00%	412.29	
25+50.00	413.07	4.00%	413.23	3.80%	12.00	412.77	12.00	3.80%	412.32	4.00%	412.16	
25+75.00	412.94	4.00%	413.10	3.80%	12.00	412.65	12.00	3.80%	412.19	4.00%	412.03	
26+00.00	412.81	4.00%	412.97	3.80%	12.00	412.52	12.00	3.80%	412.06	4.00%	411.90	
26+25.00	412.69	4.00%	412.85	3.80%	12.00	412.39	12.00	3.80%	411.93	4.00%	411.77	
26+50.00	412.56	4.00%	412.72	3.80%	12.00	412.26	12.00	3.80%	411.81	4.00%	411.65	
26+75.00	412.43	4.00%	412.59	3.80%	12.00	412.13	12.00	3.80%	411.68	4.00%	411.52	
27+00.00	412.30	4.00%	412.46	3.80%	12.00	412.01	12.00	3.80%	411.55	4.00%	411.39	
27+25.00	412.17	4.00%	412.33	3.80%	12.00	411.88	12.00	3.80%	411.42	4.00%	411.26	
27+50.00	412.05	4.00%	412.21	3.80%	12.00	411.75	12.00	3.80%	411.29	4.00%	411.13	
27+75.00	411.92	4.00%	412.08	3.80%	12.00	411.62	12.00	3.80%	411.17	4.00%	411.01	
28+00.00	411.79	4.00%	411.95	3.80%	12.00	411.49	12.00	3.80%	411.04	4.00%	410.88	
28+25.00	411.66	4.00%	411.82	3.80%	12.00	411.37	12.00	3.80%	410.91	4.00%	410.75	
28+50.00	411.53	4.00%	411.69	3.80%	12.00	411.24	12.00	3.80%	410.78	4.00%	410.62	
28+75.00	411.41	4.00%	411.57	3.80%	12.00	411.11	12.00	3.80%	410.65	4.00%	410.49	
28+76.12	411.40	4.00%	411.56	3.80%	12.00	411.11	12.00	3.80%	410.65	4.00%	410.49	
29+00.00	411.28	4.00%	411.44	3.80%	12.00	410.98	13.93	3.80%	410.45	4.00%	410.29	
29+25.00	411.15	4.00%	411.31	3.80%	12.00	410.86	15.92	3.80%	410.25	4.00%	410.09	
29+50.00	411.02	4.00%	411.18	3.80%	12.00	410.73	17.88	3.80%	410.05	4.00%	409.89	
29+75.00	410.90	4.00%	411.06	3.80%	12.00	410.60	19.81	3.80%	409.85	4.00%	409.69	
30+00.00	410.77	4.00%	410.93	3.80%	12.00	410.47	21.70	3.80%	409.65	4.00%	409.49	
30+25.00	410.65	4.00%	410.81	3.80%	12.28	410.34	23.55	3.80%	409.45	4.00%	409.29	
30+31.12	410.63	4.00%	410.79	3.80%	12.45	410.31	24.00	3.80%	409.40	4.00%	409.24	
30+50.00	410.55	4.00%	410.71	3.80%	12.99	410.22	24.00	3.80%	409.30	4.00%	409.14	
30+75.00	410.45	4.00%	410.61	3.80%	13.70	410.09	24.00	3.80%	409.18	4.00%	409.02	
30+80.00	410.44	4.00%	410.60	3.80%	13.85	410.08	24.00	3.80%	409.16	4.00%	409.00	FULL S.E.
30+85.38	410.39	4.00%	410.55	3.53%	14.00	410.06	24.00	3.53%	409.21	4.00%	409.05	
31+00.00	410.26	4.00%	410.42	2.78%	14.00	410.03	24.00	2.78%	409.36	4.00%	409.20	
31+16.63	410.15	4.00%	410.31	1.93%	14.51	410.03	24.00	1.93%	409.57	4.00%	409.41	PT
31+25.00	410.11	4.00%	410.27	1.50%	15.20	410.04	24.00	1.50%	409.68	4.00%	409.52	1.5% SE
31+50.00	410.01	4.00%	410.17	0.25%	18.57	410.12	24.00	1.50%	409.76	4.00%	409.60	
31+55.00	409.99	4.00%	410.15	0.00%	19.49	410.15	24.00	1.50%	409.79	4.00%	409.63	0% IN ONE LANE
31+75.00	409.88	4.00%	410.04	-1.00%	23.97	410.28	25.14	1.50%	409.90	4.00%	409.74	
31+85.00	409.80	4.00%	409.96	-1.50%	26.71	410.36	28.03	1.50%	409.94	4.00%	409.78	NORMAL CROWN

..\DBCONN-11-BORDER.DGN ..\DBCONN-11-SCHEDG1.DGN ..\DBCONN-11-SCHEDG2.DGN ..\DBCONN-99-MOTIF1.DGN ..\DBCONN-11-MOTIF1.DGN ..\DBCONN-11-MOTIF2.DGN ..\DBCONN-11-SCHEDG2.DGN
10-19-2011 15:22:05 BOND-HUJO \\FS-0044\VAULT_D-TRANS.87\2202-20868-001\CIVIL\CAD\99 ALL CONTRACTS\CONN-SHEETS CONTRACT II\DBCONN-11-SHT-SCHEDULE'S-2.DGN

FILE NAME = $FILE$	USER NAME = $USER$	DESIGNED - JB	REVISED -	
		DRAWN - MDN	REVISED -	
TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS	PLOT SCALE = $SCALE$	CHECKED - ACL	REVISED -	
	PLOT DATE = $DATE$	DATE - 10/21/11	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
PROPOSED RELOCATED IL ROUTE 3 INTERCHANGE

PAVEMENT ELEVATION SCHEDULES
PROPOSED ST. CLAIR AVENUE CONNECTOR

SCALE: N.T.S. | SHEET NO. 2 OF 2 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
998	82-2-1K	ST. CLAIR	353	183
		CONTRACT NO. 76E06		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		