PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS

AREA (SQ FT)	DESC
15.6	ARROW

ALIGNMENT	STATION	TYPE	AREA (SQ FT)
EX. IL RTE. 3	112+32	LT	15.6
EX. IL RTE. 3	114+32	LT	15.6
		TOTAL	31

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"

TYPE	DESC
4SW	4" SOLID WHITE
4SY	4" SOLID YELLOW
4SDW	4" SKIP-DASH WHITE
4DY	4" DOUBLE YELLOW LINE

ALIGNMENT	STATION	OFFSET	RT/LT	STATION	OFFSET	RT/LT	TYPE	LENGTH (FT)
EX. IL RTE. 3	107+15	16	RT	119+43	15	RT	4SW	1228
EX. IL RTE. 3	107+15	14	LT	114+13	35	LT	4SW	700
EX. IL RTE. 3	107+15	0	CL	112+21	2	LT	4DY	1012
EX. IL RTE. 3	107+15	0	CL	112+21	2	LT	4DY	1012
EX. IL RTE. 3	110+65	11	RT	112+21	21	RT	4SDW	39
EX. IL RTE. 3	112+21	21	RT	114+50	10	RT	4SW	229
EX. IL RTE. 3	112+21	2	LT	114+50	2	LT	4DY	458
EX. IL RTE. 3	115+26	2	LT	119+43	0	CL	4DY	830
EX. IL RTE. 3	115+26	2	RT	119+43	0	CL	4DY	846
EX. IL RTE. 3	115+64	14	LT	119+43	15	LT	4SW	378
							TOTAL	6732

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"

TYPE	DESC
12SW	12" SOLID WHITE
12SY	12" SOLID YELLOW

ALIGNMENT	STATION	OFFSET	RT/LT	STATION	OFFSET	RT/LT	TYPE	LENGTH (FT)
EX. IL RTE. 3	107+60	N/A	N/A	112+00	N/A	N/A	12SY	129
EX. IL RTE. 3	115+25	N/A	N/A	119+43	N/A	N/A	12SY	113
							TOTAL	242

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4" / GROOVING FOR RECESSED PAVEMENT MARKING 5"

TYPE	DESC
4SW	4" SOLID WHITE
4SY	4" SOLID YELLOW
4SDW	4" SKIP-DASH WHITE
4DY	4" DOUBLE YELLOW
4SDY	4" SKIP-DASH YELLOW

ALIGNMENT	STATION	OFFSET	RT/LT	STATION	OFFSET	RT/LT	TYPE	LENGTH (FT)
PR. EXCHANGE	35+12	0	LT	37+78	6	RT	4DY	532
PR. EXCHANGE	35+12	12	LT	55+44	20	LT	4SW	2036
PR. EXCHANGE	35+12	12	RT	36+68	22	RT	4SW	157
PR. EXCHANGE	35+44	0	RT	37+78	6	RT	4DY	468
PR. EXCHANGE	38+51	120	RT	44+08	23	RT	4SW	606
PR. EXCHANGE	38+55	4	RT	44+15	4	RT	4SY	445
PR. EXCHANGE	38+55	8	RT	44+15	8	RT	4SY	445
PR. EXCHANGE	38+68	9	LT	44+00	9	LT	4SW	532
PR. EXCHANGE	45+43	6	RT	49+95	5	RT	4DY	904
PR. EXCHANGE	45+43	6	RT	49+95	5	RT	4DY	904
PR. EXCHANGE	45+43	23	RT	49+60	35	RT	4SW	417
PR. EXCHANGE	45+43	9	LT	46+58	9	LT	4SW	115
PR. EXCHANGE	46+55	23	RT	47+90	23	RT	4SDW	34
PR. EXCHANGE	46+58	9	LT	47+91	10	LT	4SDW	34
PR. EXCHANGE	47+90	23	RT	49+89	23	RT	4SW	199
PR. EXCHANGE	51+19	9	RT	56+11	1	RT	4DY	984
PR. EXCHANGE	51+19	9	RT	56+11	1	LT	4DY	984
PR. EXCHANGE	51+19	9	LT	52+93	9	LT	4SW	174
PR. EXCHANGE	51+46	39	RT	55+40	20	RT	4SW	390
PR. EXCHANGE	52+93	9	LT	54+00	10	LT	4SDW	27
PR. REL. IL RTE. 3	1669+89	23	RT	1681+55	7	RT	4SW	1166
PR. REL. IL RTE. 3	1671+35	35	LT	1676+05	23	LT	4SY	482*
PR. REL. IL RTE. 3	1671+35	23	LT	1682+18	11	LT	4SY	1095
PR. REL. IL RTE. 3	1671+35	15	LT	1682+18	5	LT	4SY	1098
PR. REL. IL RTE. 3	1671+44	47	LT	1680+78	35	LT	4SW	935
PR. REL. IL RTE. 3	1682+64	7	RT	1692+94	64	RT	4SW	1054
PR. REL. IL RTE. 3	1682+80	35	LT	1692+85	122	LT	4SW	1052
PR. REL. IL RTE. 3	1683+28	23	LT	1685+28	23	LT	4SW	200
PR. REL. IL RTE. 3	1683+42	10	LT	1692+42	21	LT	4SY	898
PR. REL. IL RTE. 3	1683+42	7	LT	1692+42	17	LT	4SY	898
PR. REL. IL RTE. 3	1685+28	23	LT	1687+28	23	LT	4SDW	50
PR. REL. IL RTE. 3	1687+78	5	LT	1689+78	5	LT	4SDW	50
PR. REL. IL RTE. 3	1689+78	5	LT	1692+39	5	LT	4SW	261
RAMP A	17+25	0	CL	24+80	158	RT	4SW	853
RAMP A	17+25	16	LT	24+80	43	LT	4SY	767
RAMP A	20+85	0	CL	22+22	0	CL	4SDW	36
RAMP A	22+22	0	CL	23+97	0	CL	4SW	175
RAMP B	50+07	60	RT	58+14	0	CL	4SW	836
RAMP B	50+07	49	LT	58+14	16	LT	4SY	819
RAMP C	110+40	0	CL	119+33	0	CL	4SW	893
RAMP C	110+40	16	LT	119+62	16	LT	4SY	944
RAMP D	250+22	93	RT	258+00	0	CL	4SW	835
RAMP D	250+80	27	LT	258+00	16	LT	4SY	755
RAMP D	250+81	12	LT	252+83	12	LT	4SDW	50
CONNECTOR	20+47	89	RT	32+20	63	RT	4SW	1207
CONNECTOR	20+65	0	CL	32+10	0	CL	4DY	2291
CONNECTOR	20+66	12	LT	23+46	12	LT	4SW	282*
CONNECTOR	28+76	1	RT	30+31	12	RT	4SDW	39
CONNECTOR	30+31	12	RT	32+10	12	RT	4SW	179
WT. DRIVE	900+50	9	LT	32+40	88	LT	4SW	1094
WT. DRIVE	900+50	9	RT	23+46	12	LT	4SW	304
WT. DRIVE	900+50	0	CL	902+80	0	CL	4SDY	58
							TOTAL	32043

* NO GROOVING REQUIRED FOR THESE PAVEMENT MARKINGS

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS / GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS

AREA (SQ FT)	DESC
15.6	ARROW
25.9	TURN AND THRU ARROW

ALIGNMENT	STATION	TH/LT/RT	AREA (SQ FT)
PR. EXCHANGE	38+87	LT	15.6
PR. EXCHANGE	41+34	LT	15.6
PR. EXCHANGE	43+86	LT	15.6
PR. EXCHANGE	45+58	LT	15.6
PR. EXCHANGE	48+00	RT	15.6
PR. EXCHANGE	49+76	RT	15.6
PR. EXCHANGE	51+27	LT	15.6
PR. EXCHANGE	52+80	LT	15.6
PR. REL. IL RTE. 3	1671+59	LT	15.6
PR. REL. IL RTE. 3	1672+27	LT	15.6
PR. REL. IL RTE. 3	1683+50	LT	15.6
PR. REL. IL RTE. 3	1685+18	LT	15.6
PR. REL. IL RTE. 3	1689+90	LT	15.6
PR. REL. IL RTE. 3	1689+90	RT	15.6
PR. REL. IL RTE. 3	1692+24	LT	15.6
PR. REL. IL RTE. 3	1692+24	RT	15.6
RAMP A	22+44	RT	15.6
RAMP A	22+44	LT	15.6
RAMP A	24+35	RT	15.6
RAMP A	24+42	LT	15.6
RAMP C	119+93	RT	15.6
CONNECTOR	20+85	LT	15.6
CONNECTOR	21+65	LT	15.6
CONNECTOR	31+12	RT	15.6
CONNECTOR	31+12	LT	15.6
CONNECTOR	31+87	RT	15.6
CONNECTOR	31+87	LT	15.6
		TOTAL	421

$$$ref_list_name$$$ $$$date_time$$$ $$user$$ $$$$$$$$$$$$$$$$$dgn_name$$$$$$$$$$$$$$$$$$$$

LIN ENGINEERING, LTD.
Consulting Engineers
Chatham, Illinois
Westmont, Illinois

USER NAME = Plotted by Scott Wilkinson	DESIGNED - RK	REVISED -
	DRAWN - RK	REVISED -
PLOT SCALE = 50.0000 ' / IN.	CHECKED - ST	REVISED -
PLOT DATE = 10/17/2011	DATE - 10/21/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
PROPOSED RELOCATED ILLINOIS ROUTE 3 INTERCHANGE

PAVEMENT MARKING
SCHEDULE OF QUANTITIES

SCALE: N/A | SHEET NO. 1 OF 3 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
998	82-2-1K	ST. CLAIR	353	198

CONTRACT NO. 76E06

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT