FINAL SURVEY	SURVEYED	BY	DATE
	COMPUTED		
NOTE BOOK	TEMPLATE		
NO.	AREAS		
	AREAS CHECKED		

℄ RELOCATED IL RTE 3

RETENTION BASIN
EARTHWORK CALCULATED
SEPARATELY

INV. = 403.93
AT STA. 1671+55.95

36" PIPE CULVERT

INV. = 404.36
AT STA. 1671+38.70

EARTH EXCAVATION = 3.9 SQ FT
TOPSOIL REMOVAL = 124.8 SQ FT
EMBANKMENT = 2924.9 SQ FT

1671+50.00

ORIGINAL SURVEY	SURVEYED	BY	DATE
	COMPUTED		
NOTE BOOK	TEMPLATE		
NO.	AREAS		
	AREAS CHECKED		

℄ RELOCATED IL RTE 3

EARTHWORK QTYS. INCLUDED
IN ST. CLAIR AVE CONNECTOR
CROSS SECTIONS

EARTH EXCAVATION = 0.0 SQ FT
TOPSOIL REMOVAL = 106.9 SQ FT
EMBANKMENT = 3150.5 SQ FT

1671+00.00

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED - JB	REVISED -
		DRAWN - AG	REVISED -
	PLOT SCALE = $SCALE$	CHECKED - ACL	REVISED -
	PLOT DATE = $DATE$	DATE - 10/21/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CROSS SECTIONS
RELOCATED IL ROUTE 3

SCALE: | SHEET NO. OF SHEETS | STA. 1671+00.00 TO STA. 1671+50.00

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
998	82-2-1K	ST. CLAIR	353	296
		CONTRACT NO. 76E06		
		ILLINOIS FED. AID PROJECT		