

SUMMARY OF QUANTITIES

| SUMMARY OF QUANTITIES | | | CONSTRUCTION TYPE CODE | | | SUMMARY OF QUANTITIES | | | CONSTRUCTION TYPE CODE | | |
|-----------------------|--|--------|------------------------|-----------------|--|-----------------------|---|-------|------------------------|-----------------|--|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | 100% STATE 0014 | | CODE NO | ITEM | UNIT | TOTAL QUANTITIES | 100% STATE 0014 | |
| 20200500 | EARTH EXCAVATION (WIDENING) | CU YD | 24 | 24 | | * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 8 | 8 | |
| 20400800 | FURNISHED EXCAVATION | CU YD | 526 | 526 | | * 78100105 | RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) | EACH | 4 | 4 | |
| 35650400 | BASE COURSE WIDENING 9" | SQ YD | 177 | 177 | | * 78200410 | GUARDRAIL MARKERS, TYPE A | EACH | 14 | 14 | |
| 44004250 | PAVED SHOULDER REMOVAL | SQ YD | 118 | 118 | | * 78200520 | BARRIER WALL MARKERS, TYPE B | EACH | 8 | 8 | |
| 50102400 | CONCRETE REMOVAL | CU YD | 19.2 | 19.2 | | * 78200530 | BARRIER WALL MARKERS, TYPE C | EACH | 8 | 8 | |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 52.8 | 52.8 | | * 78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 4 | 4 | |
| 50300300 | PROTECTIVE COAT | SQ YD | 59.5 | 59.5 | | 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 670 | 670 | |
| 50500405 | FURNISHING AND ERECTING STRUCTURAL STEEL | POUND | 2790 | 2790 | | 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 12 | 12 | |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 3800 | 3800 | | * X7200200 | WIDE LOAD SIGNING | L SUM | 1 | 1 | |
| 50800515 | BAR SPLICERS | EACH | 75 | 75 | | Z0001899 | JACK AND REMOVE EXISTING BEARINGS | EACH | 10 | 10 | |
| 52000110 | PREFORMED JOINT STRIP SEAL | FOOT | 68 | 68 | | Z0001905 | STRUCTURAL STEEL REPAIR | POUND | 2730 | 2730 | |
| 52100010 | ELASTOMERIC BEARING ASSEMBLY, TYPE I | EACH | 5 | 5 | | Z0030250 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 2 | 2 | |
| 52100020 | ELASTOMERIC BEARING ASSEMBLY, TYPE II | EACH | 5 | 5 | | Z0030350 | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 2 | 2 | |
| 52100520 | ANCHOR BOLTS, 1" | EACH | 20 | 20 | | | | | | | |
| * 63000001 | STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS | FOOT | 688 | 688 | | | | | | | |
| * 63100085 | TRAFFIC BARRIER TERMINAL, TYPE 6 | EACH | 4 | 4 | | | | | | | |
| * 63100167 | TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT | EACH | 4 | 4 | | | | | | | |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 1209 | 1209 | | | | | | | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 9 | 9 | | | | | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | | | | |
| 70100405 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 | EACH | 1 | 1 | | | | | | | |
| 70100500 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326 | L SUM | 1 | 1 | | | | | | | |
| 70106500 | TEMPORARY BRIDGE TRAFFIC SIGNALS | EACH | 1 | 1 | | | | | | | |
| 70106700 | TEMPORARY RUMBLE STRIPS | EACH | 6 | 6 | | | | | | | |
| 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 0.5 | 0.5 | | | | | | | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 2015 | 2015 | | | | | | | |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 1050 | 1050 | | | | | | | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 672 | 672 | | | | | | | |
| 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 525 | 525 | | | | | | | |
| 70400200 | RELOCATE TEMPORARY CONCRETE BARRIER | FOOT | 525 | 525 | | | | | | | |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 856 | 856 | | | | | | | |
| * 78008210 | POLYUREA PAVEMENT MARKING TYPE I - LINE 4" | FOOT | 1159 | 1159 | | | | | | | |

*SPECIALTY ITEM