

WILLIAMSON COUNTY							
F. A. I. 57 ( I-57 )				F. A. P. 331 ( IL 13 )			
90% FEDERAL / 10% STATE				80% FEDERAL / 20% STATE			
ROADWAY	BRIDGE	BRIDGE	BRIDGE	LIGHTING	ROADWAY	SIGNALS	LIGHTING
STA. 403+50 TO STA. 1+00.79	100-0088 100-0089	100-0097	100-0098		STA. 1798+50 TO STA. 840+15.82	SINGLE POINT INTERSECTION	

URBAN

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE								
				0003	0010	0008	0008	0021	0003	0021	0021	
20100110	TREE REMOVAL ( 6 TO 15 UNITS DIAMETER )	UNIT	572	520						52		
20100210	TREE REMOVAL ( OVER 15 UNITS DIAMETER )	UNIT	523	462						61		
20100500	TREE REMOVAL, ACRES	ACRE	2.6	2.6								
20200100	EARTH EXCAVATION	CU YD	355,664	313,659						42,005		
20200200	ROCK EXCAVATION	CU YD	550	550								
20800150	TRENCH BACKFILL	CU YD	4,776.2	2,701.5						2,074.7		
21400100	GRADING AND SHAPING DITCHES	FOOT	30							30		
* 25000115	SEEDING, CLASS 1B	ACRE	52.00	43.75						8.25		
* 25000200	SEEDING, CLASS 2	ACRE	1.00							1.00		
* 25000310	SEEDING, CLASS 4	ACRE	21.00	21.00								
* 25000350	SEEDING, CLASS 7	ACRE	73.00	64.75						8.25		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9,247	7,927						1,320		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	6,327	5,337						990		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	6,327	5,337						990		
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	106.0	89.5						16.5		
* 25100115	MULCH, METHOD 2	ACRE	293.00	260.00						33.00		
* 25100630	EROSION CONTROL BLANKET	SQ YD	118,795	96,672						22,123		
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	1,956	1,822						134		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	7,300	6,475						825		
28000305	TEMPORARY DITCH CHECKS	FOOT	2,276	1,844						432		
28000400	PERIMETER EROSION BARRIER	FOOT	5,951	5,951								
28000500	INLET AND PIPE PROTECTION	EACH	153	125						28		
28001000	AGGREGATE ( EROSION CONTROL )	TON	198.1	196.8						1.3		
28100105	STONE RIPRAP, CLASS A3	SQ YD	966	897						69		
28100107	STONE RIPRAP, CLASS A4	SQ YD	636	121						515		

\* SPECIALTY ITEM

FILE NAME = ...D978102-shr-500_001.dgn	USER NAME = Matt Overbay	DESIGNED - MJD	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES I-57 AND IL ROUTE 13</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - EEG	REVISED -		SCALE: N/A	SHEET NO.	OF	SHEETS	STA. N/A	TO STA. N/A	WILLIAMSON	968	5
		CHECKED - BJD	REVISED -		* F.A.I. 57 AND F.A.P. 331 CONTRACT NO. 78182								
		DATE - 10/07/11	REVISED -		ILLINOIS FED. AID PROJECT								