

WILLIAMSON COUNTY							
F. A. I. 57 (I-57)				F. A. P. 331 (IL 13)			
90% FEDERAL / 10% STATE				80% FEDERAL / 20% STATE			
ROADWAY	BRIDGE	BRIDGE	BRIDGE	LIGHTING	ROADWAY	SIGNALS	LIGHTING
STA. 403+50 TO STA. 1+00.79	100-0088 100-0089	100-0097	100-0098		STA. 1798+50 TO STA. 840+15.82	SINGLE POINT INTERSECTION	

URBAN

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE									
				0003	0010	0008	0008	0021	0003	0021	0021		
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	9,860	9,860									
* 78004240	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8"	FOOT	6,334	5,674						660			
* 78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"	FOOT	856	747						109			
* 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	196	64						132			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	940	648						292			
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	65	65									
* 78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	311	131						180			
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	307	196						111			
* 78200300	PRISMATIC CURB REFLECTOR	EACH	360	92						268			
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	88	76						12			
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	59	59									
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	14	11						3			
78300100	PAVEMENT MARKING REMOVAL	SQ FT	14,427	11,289						3,138			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	586	406						180			
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	2					2					
81028340	UNDERGROUND CONDUIT, PVC, 1 1/2" DIA.	FOOT	1,038								1,038		
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	1,441					762			296	383	
81028360	UNDERGROUND CONDUIT, PVC, 2 1/2" DIA.	FOOT	64								64		
81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	1,779					428			1,338	13	
81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	10								10		
81100800	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., GALVANIZED STEEL	FOOT	538								538		
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	890					890					
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	10					10					
81300610	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 14" X 12" X 6"	EACH	6								6		
81400100	HANDHOLE	EACH	9								9		

* SPECIALTY ITEM

FILE NAME = ... \D978182-shc-S00.011.dgn	USER NAME = Matt Overbey	DESIGNED - MJO	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES I-57 AND IL ROUTE 13				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - EEG	REVISED -		SCALE: N/A	SHEET NO.	OF	SHEETS	STA. N/A	TO STA. N/A	WILLIAMSON	968	15
		CHECKED - BJD	REVISED -										
		DATE - 10/07/11	REVISED -										
											CONTRACT NO. 78182		
ILLINOIS FED. AID PROJECT													