

WILLIAMSON COUNTY							
F. A. I. 57 (I-57)				F. A. P. 331 (IL 13)			
90% FEDERAL / 10% STATE				80% FEDERAL / 20% STATE			
ROADWAY	BRIDGE	BRIDGE	BRIDGE	LIGHTING	ROADWAY	SIGNALS	LIGHTING
STA. 403+50 TO STA. 1+00.79	100-0088 100-0089	100-0097	100-0098		STA. 1798+50 TO STA. 840+15.82	SINGLE POINT INTERSECTION	

URBAN

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE									
				0003	0010	0008	0008	0021	0003	0021	0021		
* 85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1									1	
* 86200300	UNINTERRUPTIBLE POWER SUPPLY, EXTENDED	EACH	1									1	
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	3,892									3,892	
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,159									2,159	
* 87301800	ELECTRIC CABLE IN CONDUIT, SERVICE NO. 4 2C	FOOT	317									317	
* 88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	14									14	
* 88200100	TRAFFIC SIGNAL BACKPLATE	EACH	14									14	
88500525	INDUCTION LOOP DETECTOR AMPLIFIER WITH SYSTEM OUTPUT	EACH	4									4	
88600100	DETECTOR LOOP, TYPE I	FOOT	1,906									1,906	
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2									2	
XX006653	FENCE (SPECIAL)	FOOT	2,166	961							1,205		
XX007023	STAINING CONCRETE STRUCTURES	SQ YD	1,581		1,581								
<del>Z0023500</del>	<del>FILLING EXISTING CULVERTS</del>	CU YD	140.0								140.0		
X0325201	SHOULDER RUMBLE STRIP REMOVAL	SQ YD	242	242									
X0325613	REMOVE SURFACE MOUNT LANE SEPARATOR	FOOT	200								200		
X0326671	CONCRETE SURFACE COLOR TREATMENT	SQ FT	1,417		1,417								
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	1,149		945	109	95						
X4200400	PORTLAND CEMENT CONCRETE PAVEMENT 8" (SPECIAL) WITH INTEGRAL CURB	SQ YD	4,670								4,670		
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	10,369	8,755							1,614		
X5011100	FOUNDATION REMOVAL	EACH	1	1									
X5015225	PIPE CULVERT REMOVAL (SPECIAL)	FOOT	21								21		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		0.94	0.02	0.04						
<del>X5051402</del>	<del>FURNISHING AND ERECTING STRUCTURAL STEEL BRIDGE NO. 2</del>	L SUM	1										
<del>X5051403</del>	<del>FURNISHING AND ERECTING STRUCTURAL STEEL BRIDGE NO. 3</del>	L SUM	1										
50800530	MECHANICAL SPLICERS	EACH	654			292	362						

\* SPECIALTY ITEM

FILE NAME = ...D0978182-sht-500_013.dgn	USER NAME = Matt Overbey	DESIGNED - MJO	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES I-57 AND IL ROUTE 13</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 50,0000' / IN.	DRAWN - EEG	REVISED -		SCALE: N/A	SHEET NO.	OF	SHEETS	STA. N/A	TO STA. N/A	WILLIAMSON	968	17
	PLOT DATE = 10/19/2011	CHECKED - BJD	REVISED -								CONTRACT NO. 78182		
		DATE - 10/07/11	REVISED -								ILLINOIS FED. AID PROJECT		