



F.A.I. 57 (I-57) - TYPICAL #4
 STA. 1480+20.15 TO P.T. STA. 1484+40.06

NOTES:

1. SEE ROADWAY PLAN AND PROFILE, INTERSECTION DETAILS, AND SUPERELEVATION RATE CHARTS FOR WIDTH AND S.E. TRANSITION DETAILS.
2. EXISTING PIPE UNDERDRAINS, OUTLET PIPES, AND HEADWALLS TO BE REMOVED. COST INCLUDED IN EARTH EXCAVATION.
3. SEE SHEET 3 FOR MIXTURE REQUIREMENTS.

- PAVEMENT REMOVAL
- PAVED SHOULDER REMOVAL

EXISTING LEGEND

- ① EXISTING 10" PCC PAVEMENT
- ⑤ EXISTING HMA SURFACE, 4"
- ⑦ EXISTING HMA SHOULDER, 8"
- ⑧ EXISTING AGGREGATE BASE
- ⑨ EXISTING PIPE UNDERDRAINS, 4"

PROPOSED LEGEND

- ① HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 16 3/4"
- ② HOT-MIX ASPHALT SHOULDERS, 16 3/4"
- ③ SUBBASE GRANULAR MATERIAL, TYPE A, 12"
- ⑤ PIPE UNDERDRAINS 4"
- ⑨ CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT

FILE NAME = ...AD978182-sht-typical-157_004.dgn	USER NAME = Brad Downen	DESIGNED - MJO	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TYPICAL SECTION INTERSTATE 57	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - RAH	REVISED -			* (X1-6-2)HBK-2, HB-1,2; (X-1)R-1	WILLIAMSON	968	26	
		CHECKED - BJD	REVISED -			* F.A.I. 57 AND F.A.P. 331	CONTRACT NO. 78182			
		DATE - 10/07/11	REVISED -			ILLINOIS FED. AID PROJECT				
SCALE: _____						SHEET NO. _____ OF _____ SHEETS		STA. _____ TO STA. _____		