

TREE REMOVAL

STATION / LOCATION	TREE REMOVAL (6-15 UNITS)	TREE REMOVAL (OVER 15 UNITS)	TREE REMOVAL ACRES	
	(UNITS)	(UNITS)	(ACRES)	
IL RTE 13				
1819+32	151' LT	10		
1819+68	199' RT	12		
1820+28	134 LT	10		
1820+42	122' RT		16	
1825+63	107' RT		28	
830+08	76' RT	14		
830+41	86' RT		17	
833+28	72' RT	6		
RAMP A				
11+06	23' LT		22	
11+58	18' LT		18	
11+85	35' LT	15		
12+17	120' LT		17	
12+26	140' LT	8		
12+41	55' LT	7		
12+46	70' LT	7		
12+65	169' LT	12		
12+74	152' LT	13		
13+11	112' LT	6		
13+15	110' LT	7		
13+22	117' LT	6		
13+22	117' LT	6		
15+74	29' LT	10		
15+87	147' LT	6		
15+87	147' LT	6		
15+87	147' LT	6		
RAMP B				
6+29	41' RT	6		
6+29	41' RT	6		
6+47	6' RT	8		
6+88	63' RT	10		
6+88	63' RT	10		
7+18	72' RT	8		
7+19	73' RT	6		
7+19	73' RT	6		
7+33	73' RT	6		
7+33	73' RT	7		
7+73	77' RT	14		
8+56	96' RT	6		
8+75	99' RT	8		
8+82	94' RT	6		
8+90	84' RT	8		
9+24	114' RT		16	
16+11	79' LT	6		
16+13	81' LT	6		
16+15	77' LT	11		
16+82	112' RT		18	
16+98	43' LT		22	
17+02	17' LT		24	
17+24	81' LT		28	
17+25	29' LT		20	
17+95	42' LT		20	
18+24	14' LT	15		
18+33	228' LT		18	
19+03	8' RT	6		
19+03	8' RT	6		
19+71	186' LT		18	
21+13	85' LT		20	
21+29	63' LT		22	
SUBTOTALS		332	344	0

TREE REMOVAL (CONTINUED)

STATION / LOCATION	TREE REMOVAL (6-15 UNITS)	TREE REMOVAL (OVER 15 UNITS)	TREE REMOVAL ACRES	
	(UNITS)	(UNITS)	(ACRES)	
RAMP C				
2+44	26' RT		24	
5+10	68' RT		20	
6+29	87' LT		24	
10+23	186' RT	14		
10+69	148' RT	6		
10+69	148' RT	6		
10+69	148' RT	6		
12+20	113' RT	12		
12+20	113' RT	12		
12+22	94' RT	12		
12+75	79' RT	12		
12+75	79' RT	15		
12+92	97' RT	14		
13+19	86' RT	6		
13+19	86' RT	8		
13+19	86' RT	12		
13+67	113' RT	10		
13+67	113' RT	10		
13+67	113' RT	14		
13+73	119' RT	12		
SUBTOTALS		181	68	0

TREE REMOVAL (CONTINUED)

STATION / LOCATION	TREE REMOVAL (6-15 UNITS)	TREE REMOVAL (OVER 15 UNITS)	TREE REMOVAL ACRES	
	(UNITS)	(UNITS)	(ACRES)	
RAMP D				
120+43	223' LT	12		
124+13	153' LT		18	
124+47	7' RT	9		
124+70	56' RT	6		
124+70	56' RT	10		
125+04	157' LT		18	
127+75	71' LT	12		
128+08	3' LT		24	
RAMP J				
19+82	25' RT		24	
BITTLE PLACE				
11+64	25' RT		27	
TOTALS		562	523	0.9

SEEDING

STATION / LOCATION	SEEDING CLASS 1B	SEEDING CLASS 4	SEEDING CLASS 7	TEMPORARY EROSION CONTROL SEEDING	NITROGEN FERTILIZER NUTRIENT	PHOSPHOROUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH METHOD 2		
										(ACRE)	(ACRE)
F. A. I. 57											
403+50.00	-	415+00.00	1.75		1.75	175	280	210	210	3.5	7.0
415+00.00	-	419+77.93	1.00		1.00	100	160	120	120	2.0	4.0
1461+04.83	-	1471+00.00	2.00		2.00	200	320	240	240	4.0	8.0
1471+00.00	-	1485+00.00	4.50		4.50	450	720	540	540	9.0	18.0
1485+00.00	-	1497+00.00	3.75		3.75	375	600	450	450	7.5	15.0
1497+00.00	-	1510+00.00	2.25		2.25	225	360	270	270	4.5	9.0
1510+00.00	-	1510+12.28	0.25		0.25	25	40	30	30	0.5	1.0
1510+06.21	-	1513+00.00	0.25		0.25	25	40	30	30	0.5	1.0
IL RTE 13											
1798+50.00	-	1805+50.00	1.50		1.50	150	240	180	180	3.0	6.0
1805+50.00	-	1819+67.24	3.00		3.00	300	480	360	360	6.0	12.0
1819+67.24	-	1830+11.87	2.25		2.25	225	360	270	270	4.5	9.0
830+00.00	-	833+00.00	0.75		0.75	75	120	90	90	1.5	3.0
833+00.00	-	841+34.46	0.75		0.75	75	120	90	90	1.5	3.0
RAMP A			4.00		4.00	400	640	480	480	8.0	16.0
RAMP B			4.75		4.75	475	760	570	570	9.5	19.0
RAMP C			4.00		4.00	400	640	480	480	8.0	16.0
RAMP D			7.75		7.75	775	1,240	930	930	15.5	31.0
RAMP I			2.75		2.75	275	440	330	330	5.5	11.0
RAMP J			4.50		4.50	450	720	540	540	9.0	18.0
AREA 5 (OUTSIDE RAMP D)				5.00	5.00	500	200				20.0
AREA 6 (OUTSIDE RAMP C)				7.50	7.50	750	300				30.0
AREA 9 (OUTSIDE RAMP B)				4.25	4.25	425	170				17.0
AREA 15 (OUTSIDE RAMP A)				4.25	4.25	425	170				17.0
BITTLE PLACE			0.25		0.25	25	40	30	30	0.5	1.0
TOTALS			52.00	21.00	73.00	7,300	9,160	6,240	6,240	104.0	292.0

* SEE GRADING PLAN FOR AREA LOCATIONS

FILE NAME = ...D978182-sh1-Schedule.dgn

USER NAME = Matt Overbey

DESIGNED - MJO

REVISED -

PLOT SCALE = 50.0000' / 1" IN.

DRAWN - EEG

REVISED -

PLOT DATE = 10/19/2011

CHECKED - BJD

REVISED -

DATE - 10/07/11

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	0X1-6-2H8K-2, HB-1,2; 0X-1R-1	WILLIAMSON	968	57
* F.A.I. 57 AND F.A.P. 331			CONTRACT NO. 78182	
ILLINOIS FED. AID PROJECT				