

DRAINAGE REMOVALS

STATION / LOCATION	FOR INFORMATION ONLY							TRENCH BACKFILL (CU YD)	
	MATERIALS	SIZE (INCH)	PIPE CULVERT REMOVAL (FOOT)	PIPE CULVERT REMOVAL (SPECIAL) (FOOT)	REMOVING MANHOLES (EACH)	REMOVING INLETS (EACH)	PLUG AND ABANDON EXISTING PIPE (CU YD)		
F. A. I. 57									
408+51	CL	RCP	24	39		2		4.2	
1474+33	97' LT					1			
1474+60	10' RT	RCP	24	201					
1474+99	93' RT	CMP	24	158					
1475+14	96' LT	RCP	24	153					
1475+48	12' LT	RCP	24	201					
1475+95	97' LT					1			
1477+01	91' LT	RCP	24	14		1			
1477+01	CL	RCP	24	34		1			
1477+01	19' LT					1			
1504+91	10' RT					1		5.6	
1504+91	7' RT	RCP	24	7				8.6	
1505+05	12' RT	RCP	24	29				35.4	
1505+20	13' RT				1			5.6	
1506+01	10' RT	RCP	24	163				182.6	
1506+82	7' RT					1		5.1	
1506+94	3' RT	RCP	24	25				28.0	
1507+06	CL	RCP	18	12					
1508+25	CL	RCP	18	12					
1508+38	CL	RCP	18	12					
1508+70	LT	RCP	48	3					
1509+50	CL	RCP	18	12					
1509+98	CL	RCP	15	83				61.5	
1545+79	CL					1			
1545+80	2' LT	RCP	12	2					
1545+87	4' RT	RCP	36	21					
1545+98	6' RT	RCP	12	16				15.4	
1546+04	CL					1		6.1	
1563+70	CL	RCP	48	5					
1563+71	CL					1			
IL RTE 13									
1802+13	CL	RCP	42	111			54	208.6	
1802+15	115' LT	RCP	38 x 60	100				10.9	
1802+34	68' LT				1				
1802+59	72' LT	RCP	24	57				62.6	
1802+94	76' LT					1		12.8	
1803+99	3' RT					1		3.6	
1804+01	RT	RCP	15/18	113				31.1	
1808+08	CL	CMP	24	123				165.4	
1810+43	LT	RCP	18	10					
1811+19	CL	RCP/CMP	24	133				86.0	
1811+92	LT	RCP	18	10					
1812+09	RT	RCP	15	90			5	23.1	
1812+99	CL					1		3.7	
1816+59	3' LT	CMP	24	170				143.4	
1823+19	76' LT					1		1.9	
1823+50	83' LT	RCP	24	53					
1823+78	90' LT				1				
1823+83	134' LT	RCP/CMP	72	69	21				
831+73	127' LT	CMP	8	36					
832+70	2' RT	CMP	54	35			81	33.4	
832+97	80' LT					1			
832+97	106' LT					1			
832+97	92' LT	CMP	42	41				5.3	
834+81	96' LT	CMP	18	74				15.9	
839+00	74' LT	CMP	24	200					
RAMP B									
11+35	44' RT	RCP	42	346				181.7	
12+96	29' LT					1			
14+30	56' LT	RCP	36	274					
18+25	234' RT	RCP	24	63					
SUBTOTALS				3,310	21	3	19	140	1,347.5

DRAINAGE REMOVALS (CONTINUED)

STATION / LOCATION	FOR INFORMATION ONLY							TRENCH BACKFILL (CU YD)	
	MATERIALS	SIZE (INCH)	PIPE CULVERT REMOVAL (FOOT)	PIPE CULVERT REMOVAL (SPECIAL) (FOOT)	REMOVING MANHOLES (EACH)	REMOVING INLETS (EACH)	PLUG AND ABANDON EXISTING PIPE (CU YD)		
RAMP C									
6+20	461' RT	RCP	24	87					
6+47	381' RT	RCP	36	159					
7+94	83' RT	RCP	36	135					
8+58	108' RT					1			
9+54	129' RT	RCP	36	195					
RAMP D									
112+75	10' RT					1		1.8	
113+50	95' RT					1			
113+88	22' RT	ELLIPTICAL RCP	15	220				13.0	
126+61	280' LT	RCP	24	148					
RAMP J									
18+70	134' LT	CMP	12	20					
TEMPORARY DIAMOND RAMP A		RCP	24	116					
TEMPORARY DIAMOND RAMP B		RCP	15	68					
TEMPORARY DIAMOND RAMP C		RCP	18	84					
TOTALS				4,542	21	3	22	140	1,362.3