

**TEMPORARY PAVING (CONTINUED)**

STATION / LOCATION			SHOULDER RUMBLE STRIP REMOVAL	PAVEMENT REMOVAL	HMA PAVEMENT (FULL DEPTH), 10"	HMA PAVEMENT (FULL DEPTH), 12"	SUBBASE GRANULAR MATERIAL, TYPE B 4"	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	BITUMINOUS MATERIALS (PRIME COAT)
STATION	TO	STATION	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(SQ YD)	(GAL)
STAGE 1B										
IL 13										
1810+18.00	-	1812+04.51		392	392		392			173
1812+63.00	-	1815+34.98		522	522		522			230
1815+06.35	-	1815+36.35		100	100		100			44
STAGE 1B SUBTOTALS			0	1,014	1,014	0	1,014	0.0	0	447
STAGE 2										
F. A. I. 57										
396+60.00	-	400+00.00	RT			375	432			191
400+00.00	-	403+50.00	RT	252		723	781			344
1480+65.00	-	1483+08.00	RT					105.0	470	
1481+80.00	-	1485+00.00	RT	463		463	506			223
1485+00.00	-	1485+50.00	RT	26		26	35			16
1496+00.00	-	1497+00.00	RT	115		115	132			59
1497+00.00	-	1510+00.00	RT	781		781	789			348
1497+59.00	-	1500+00.00	RT					204.2	243	
STAGE 2 SUBTOTALS			0	1,638	0	2,483	2,676	309.2	713	1,181
TOTALS			242	19,148	10,273	10,179	22,592	345.8	1,057	9,963

FILE NAME = ...D978182-sht-Schedule.dgn

USER NAME = Matt Overbey  
 PLOT SCALE = 50.0000' / IN.  
 PLOT DATE = 10/19/2011

DESIGNED - MJO  
 DRAWN - EEG  
 CHECKED - BJD  
 DATE - 10/07/11

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	0X1-6-2)HBK-2, HB-1,2; (1X-1R-1	WILLIAMSON	968	71
* F.A.I. 57 AND F.A.P. 331			CONTRACT NO. 78182	
ILLINOIS FED. AID PROJECT				