

**PAVEMENT WIDENING**

STATION / LOCATION		POLYMERIZED LEVELING BINDER (MACHINE METHOD), N105	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	
STATION	TO	STATION	(TON)	(TON)	(SQ YD)
PRE-STAGE A					
F. A. I. 57					
1507+50.00	-	1511+25.00		88.7	
IL 13					
832+64.00	-	835+43.00		12.0	
PRE-STAGE A SUBTOTALS			0.0	100.7	0
PRE-STAGE B					
F. A. I. 57					
1507+00.00	-	1513+00.00		70.1	
RAMP A					
23+50.00	-	27+50.00	LT	52.3	
PRE-STAGE B SUBTOTALS			0.0	122.4	0
STAGE 1A					
IL 13					
1804+64.00	-	1805+40.00	LT	13.2	
1819+67.00	-	1820+84.00	LT	59.8	
1819+67.00	-	1820+81.00	RT	6.1	
1821+50.00	-	1822+16.00	LT	19.8	
1821+83.00	-	1822+70.00	RT	11.2	
832+64.00	-	840+16.00	LT	58.8	
STAGE 1A SUBTOTALS			0.0	168.9	0
STAGE 1B					
IL 13					
1803+02.00	-	1803+50.00	LT	7.9	
1821+50.00	-	1822+16.00	LT	5.9	
1821+50.00	-	1822+69.00	RT	26.9	
832+64.00	-	835+43.00	LT	4.4	
STAGE 1B SUBTOTALS			0.0	45.1	0
STAGE 2					
F. A. I. 57					
1480+65.00	-	1483+08.00	RT	105.0	470
1497+59.00	-	1500+00.00	RT	65.3	243
RAMP D					
116+00.00	-	118+00.00	LT	33.5	
STAGE 2 SUBTOTALS			0.0	203.8	713
STAGE 3					
F. A. I. 57					
1474+13.00	-	1475+50.00	RT	23.8	
STAGE 3 SUBTOTALS			23.8	0.0	0
STAGE 3-1					
RAMP C					
16+00.00	-	18+50.00		13.0	154
STAGE 3-1 SUBTOTALS			13.0	0.0	154
STAGE 4					
RAMP D					
116+00.00	-	118+00.00			192
STAGE 4 SUBTOTALS			0.0	0.0	192
STAGE 5					
F. A. I. 57					
1507+00.00	-	1513+00.00	LT		834
1507+97.00	-	1513+00.00	RT	12.5	148
IL 13					
1802+92.00	-	1803+62.00	LT	16.5	
1804+64.00	-	1805+40.00	LT		157
832+64.00	-	835+43.00			878
RAMP A					
23+50.00	-	27+50.00			40
STAGE 5 SUBTOTALS			16.5	12.5	1,223
TOTALS			53.3	653.4	2,282

\* THESE QUANTITIES ARE IN ADDITION TO ANY FULL DEPTH PAVEMENT QUANTITIES

**TEMPORARY RAMPS**

STATION / LOCATION		TEMPORARY RAMPS	
STATION	TO	STATION	(SQ YD)
PRE-STAGE B			
RAMP A			
26+00.00	-	26+32.13	19
RAMP B			
3+82.00	-	4+02.00	RT 112
PRE-STAGE B SUBTOTALS			131
STAGE 1			
F. A. I. 57			
407+77.24	-	408+50.00	RT 98
1465+00.00	-	1465+10.00	LT 67
1487+90.00	-	1488+61.39	200
1492+87.35	-	1493+50.00	156
1507+00.00	-	1507+10.00	LT 34
RAMP A			
12+43.00	-	12+53.00	47
26+22.00	-	26+32.00	LT 14
RAMP A-R			
1+93.00	-	2+03.00	34
RAMP B			
19+14.00	-	19+24.00	47
RAMP B-R			
1+82.00	-	1+92.00	34
RAMP I			
13+15.00	-	13+46.34	47
15+20.57	-	15+52.00	47
RAMP J			
8+40.00	-	8+75.64	43
10+93.38	-	11+18.00	35
STAGE 1A			
IL 13			
1798+50.00	-	1798+60.00	LT 35
1798+50.00	-	1798+60.00	RT 34
1802+92.00	-	1803+02.00	LT 34
1803+30.00	-	1803+46.00	RT 54
1805+34.00	-	1805+50.00	RT 55
1805+40.00	-	1805+50.00	LT 47
1819+67.00	-	1819+80.00	RT 55
1819+67.00	-	1819+83.00	LT 59
1822+15.00	-	1822+31.00	LT 61
1822+68.00	-	1822+84.00	RT 71
832+48.00	-	832+64.00	LT 54
836+55.00	-	836+65.00	RT 33
STAGE 1B			
IL 13			
1798+50.00	-	1798+60.00	LT 45
1798+50.00	-	1798+60.00	RT 27
1802+90.00	-	1803+02.00	LT 32
1803+38.00	-	1803+50.00	RT 32
1805+34.00	-	1805+50.00	RT 43
1805+40.00	-	1805+50.00	LT 14
1819+67.00	-	1819+87.00	LT 89
1819+67.00	-	1819+87.00	RT 27
1822+15.00	-	1822+31.00	LT 43
1822+68.00	-	1822+84.00	RT 23
832+48.00	-	832+64.00	LT 22
836+55.00	-	836+65.00	RT 15
STAGE 1 SUBTOTALS			1,907

**TEMPORARY RAMPS**

STATION / LOCATION		TEMPORARY RAMPS	
STATION	TO	STATION	(SQ YD)
STAGE 2			
F. A. I. 57			
408+30.00	-	408+50.00	RT 67
1506+70.00	-	1507+10.00	LT 138
1507+00.00	-	1507+10.00	RT 35
RAMP C			
3+00.00	-	3+10.00	47
RAMP C-R			
1+82.00	-	1+92.00	34
RAMP D			
118+00.00	-	118+50.00	LT 82
127+16.00	-	127+26.00	47
RAMP D-R			
3+67.00	-	3+77.00	33
STAGE 2 SUBTOTALS			483
STAGE 3			
F. A. I. 57			
408+30.00	-	408+50.00	RT 40
1506+78.00	-	1507+10.00	RT 43
STAGE 3-1			
RAMP C			
17+84.00	-	18+16.00	LT 96
STAGE 3 SUBTOTALS			179
TOTALS			2,700

FILE NAME = ...D978182-sht-Schedule.dgn

USER NAME = Matt Overbey  
 PLOT SCALE = 50.0000' / IN.  
 PLOT DATE = 10/19/2011

DESIGNED - MJO  
 DRAWN - EEC  
 CHECKED - BJD  
 DATE - 10/07/11

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	(X1-6-2)HBK-2, HB-1,2; (X-1R-1	WILLIAMSON	968	73
* F.A.I. 57 AND F.A.P. 331 CONTRACT NO. 78182				
ILLINOIS FED. AID PROJECT				