



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 9, 2012

SUBJECT: FAP Route 885 (IL 146)
Project F-0885 (044)
Section 13 B-1
Union County
Contract No. 78255
Item No. 96, January 20, 2012 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised sheet 3 of the Plans.
3. Revised page i of the Table of Contents to the Special Provisions.
4. Revised pages 4 and 70 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Omer M. Osman, Region 5, District 9; Mike Renner; D.Carl Puzey;
Estimates

TBW:DB:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 78255

State Job # - C-99-043-11
 PPS NBR - 9-00303-0000
 County Name - UNION- -
 Code - 181 - -
 District - 9 - -
 Section Number - 13B-1

Project Number
 F-0885/044/

Route
 FAP 885

*REVISED: JANUARY 06, 2012

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0055905	TEMP CONSTR FENCE	FOOT	200.000				
20100110	TREE REMOV 6-15	UNIT	25.000				
20700220	POROUS GRAN EMBANK	CU YD	406.000				
25000115	SEEDING CL 1B	ACRE	0.100				
25000350	SEEDING CL 7	ACRE	0.100				
25000400	NITROGEN FERT NUTR	POUND	9.000				
25000500	PHOSPHORUS FERT NUTR	POUND	9.000				
25000600	POTASSIUM FERT NUTR	POUND	9.000				
25000700	AGR GROUND LIMESTONE	TON	0.200				
25100115	MULCH METHOD 2	ACRE	0.100				
28100707	STONE DUMP RIP CL A4	SQ YD	12.000				
40200100	AGG SURF CSE A	TON	13.000				
40300100	BIT MATLS PR CT	GALLON	103.000				
40603245	P HMA BC IL19.0 N105	TON	71.000				
40603550	P HMA SC "D" N105	TON	18.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 78255

State Job # - C-99-043-11
 PPS NBR - 9-00303-0000
 County Name - UNION- -
 Code - 181 - -
 District - 9 - -
 Section Number - 13B-1

Project Number
 F-0885/044/

Route
 FAP 885

*REVISED: JANUARY 06, 2012

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
42300100	PCC DRIVEWAY PAVT 5	SQ YD	58.000				
42400100	PC CONC SIDEWALK 4	SQ FT	592.000				
44000100	PAVEMENT REM	SQ YD	206.000				
44000200	DRIVE PAVEMENT REM	SQ YD	54.000				
44000500	COMB CURB GUTTER REM	FOOT	99.000				
44000600	SIDEWALK REM	SQ FT	539.000				
50100100	REM EXIST STRUCT	EACH	1.000				
50200100	STRUCTURE EXCAVATION	CU YD	681.000				
50800205	REINF BARS, EPOXY CTD	POUND	1,080.000				
50901720	BICYCLE RAILING	FOOT	55.000				
54003000	CONC BOX CUL	CU YD	14.100				
54011004	PCBC 10X4	FOOT	86.000				
54248510	CONCRETE COLLAR	CU YD	5.700				
550A0120	STORM SEW CL A 1 24	FOOT	11.000				
550A0190	STORM SEW CL A 1 48	FOOT	64.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 78255

State Job # - C-99-043-11
 PPS NBR - 9-00303-0000
 County Name - UNION- -
 Code - 181 - -
 District - 9 - -
 Section Number - 13B-1

Project Number
 F-0885/044/

Route
 FAP 885

*REVISED: JANUARY 06, 2012

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
55101200	STORM SEWER REM 24	FOOT	6.000				
55101900	STORM SEWER REM 48	FOOT	18.000				
60224030	MAN TA 6 DIA T15F&L	EACH	1.000				
60224446	MAN TA 7 DIA T1F CL	EACH	1.000				
60224459	MAN TA 8 DIA T1F CL	EACH	1.000				
60404800	FR & GRATES T11	EACH	1.000				
60605000	COMB CC&G TB6.24	FOOT	99.000				
67100100	MOBILIZATION	L SUM	1.000				
70101830	TRAF CONT-PROT BLR 21	L SUM	1.000				
70102622	TR CONT & PROT 701502	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	40.000				
*REV 70106800	CHANGEABLE MESSAGE SN	CAL MO	2.000				
70300100	SHORT TERM PAVT MKING	FOOT	16.000				
70300220	TEMP PVT MK LINE 4	FOOT	103.000				
78001110	PAINT PVT MK LINE 4	FOOT	103.000				

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
UTILITIES.....	1
TRAFFIC CONTROL PLAN	2
TWO WEEK NOTIFICATION PRIOR TO STARTING WORK.....	3
PORTABLE CHANGEABLE MESSAGE SIGNS	4
BOX CULVERT REMOVAL AND REPLACEMENT	4
ASSEMBLE AND MATCH MARK PRECAST CONCRETE BOX CULVERT	4
POTATO BARN AIR CONDITIONING AND KITCHEN VENT PROTECTION.....	5
PRECAST BOX CULVERTS	5
AGREEMENT TO PLAN QUANTITY (BDE).....	5
CONSTRUCTION AIR QUALITY - DIESEL VEHICLE EMISSIONS CONTROL (BDE)	6
CONSTRUCTION AIR QUALITY - IDLING RESTRICTIONS (BDE).....	7
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	8
FLAGGER AT SIDE ROADS AND ENTRANCES (BDE)	16
FRICTION AGGREGATE (BDE)	17
HOT-MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS (BDE)	19
METAL HARDWARE CAST INTO CONCRETE (BDE).....	20
PAYMENTS TO SUBCONTRACTORS (BDE)	21
PORTLAND CEMENT CONCRETE (BDE)	22
PORTLAND CEMENT CONCRETE SIDEWALK (BDE)	55
RECLAIMED ASPHALT PAVEMENT (RAP) (BDE)	56
SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE).....	63
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	64
TEMPORARY EROSION AND SEDIMENT CONTROL (BDE).....	64
TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE)	64
UTILITY COORDINATION AND CONFLICTS (BDE).....	65
WORKING DAYS (BDE)	70
DELAYED START OF CONTRACT	70

Revised 01/09/12

This additional notification is required so that the public can be notified of the pending construction.

PORTABLE CHANGEABLE MESSAGE SIGNS

This work consists of furnishing, placing, and maintaining changeable message sign(s) according to the Standard Specifications and the following:

A total of 4 changeable message signs shall be required in this contract. All signs must be in place and operational for a minimum of 14 calendar days prior to lane closures. Each sign shall state the day work will begin and delays are possible. The exact message will be approved by the Engineer. The Contractor may be required to relocate each sign multiple times during the contract at his or her expense. The exact location of the placement of these signs shall be determined in the field by the Engineer. Two recommended locations are at the intersection of IL 146 with IL 3 and with US 51.

The furnishing, placing, and maintaining of portable changeable message sign(s) shall be paid for per calendar month as CHANGEABLE MESSAGE SIGN.

BOX CULVERT REMOVAL AND REPLACEMENT

IL 146 shall be allowed to be closed for the removal and replacement of the existing culvert, storm sewer relocation, and backfilling. A closure of IL 146 at the project location shall be permitted for one 72 consecutive hour period of time. Outside of this time, IL 146 shall be open to at least one lane of traffic, subject to Article 108.09 of the Standard Specifications. This closure shall not be permitted on any Holiday weekend as stated in article 107.09 of the Standard Specifications for Road and Bridge Construction. After the roadway is opened to traffic, the cast-in-place headwalls/wingwalls of the box shall be installed along with any other applicable items.

A quantity of Temporary Construction Fence has been included in the plans. It shall be constructed as a barrier to pedestrians around any open trenches when workers are not present or as directed by the Engineer.

A schedule for the closure of IL 146 shall be submitted to the Engineer two weeks in advance for approval and for the engineer to give notice to the city. The contact person for the City of Anna is the City Administrator, Steve Guined. His phone number is (618)833-8528.

ASSEMBLE AND MATCH MARK PRECAST CONCRETE BOX CULVERT

Precast concrete box culverts shall be constructed according to Section 540 of the Standard Specifications for Road and Bridge Construction, Adopted January 1, 2012, except as modified by this Special Provision. This Special Provision applies to any proposed precast concrete box culverts that are larger than 6' x 6' in at least one dimension.

The contractor shall assemble and match mark the precast concrete box culvert sections prior to the shipment of these components from the producer, as directed by the Engineer, in order to secure a proper fit on each joint. Any sections that do not provide a proper fit shall be rejected by the Engineer and replaced by the Contractor with no additional compensation.

The assembling and match marking shall be witnessed by the Contractor.

This work will not be paid for separately, but shall be considered included in the unit price for Precast Concrete Box Culverts of the size specified.

Revised 01/09/12

The Contractor shall fully cooperate with the Department in its efforts to recover from another party any money paid to the Contractor for delay damages under this Provision.”

WORKING DAYS (BDE)

Effective: January 1, 2002

The Contractor shall complete the work within **40** working days.

DELAYED START OF CONTRACT

The Department is waiving the 10 day start-up requirement for Contractors to begin work as stated in Article 108.03 of the Standard Specifications. Furthermore, the Department will not allow work to commence until all Anna-Jonesboro schools have closed for summer break. According to the school district, this date will be no later than June 1, 2012.

Revised 01/09/12