

STATE JOB # - - - -

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT NUMBER - SC066

ECMS081 DTGECM03 ECMR003 PAGE 1  
RUN DATE - 01/17/12  
RUN TIME - 111506

COUNTY NAME	CODE	DIST	AIRPORT NAME	FED PROJECT	ILL PROJECT
ST CLAIR	163	08	MIDAMERICA ST. LOUIS	3-17-0146-XX	BL-V -4061

\*\*\*\*\* BASE \*\*\*\*\*

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR108108	1/C #8 5 KV UG CABLE	L.F.	1,025.000	X	=		
AR108602	3/C #2 600 V UG CABLE	L.F.	354.000	X	=		
AR108606	3/C #6 600 V UG CABLE	L.F.	70.000	X	=		
AR108706	1/C #6. COUNTERPOISE	L.F.	1,014.000	X	=		
AR110202	2" PVC DUCT, DIRECT BURY	L.F.	692.000	X	=		
AR110501	1-WAY CONC. ENCASED DUCT	L.F.	305.000	X	=		
AR110502	2-WAY CONCRETE ENCASED DUCT	L.F.	295.000	X	=		
AR110503	3-WAY CONCRETE ENCASED DUCT	L.F.	38.000	X	=		
AR110610	ELECTRICAL HANDHOLE	EACH	2.000	X	=		
AR125415	MITL-BASE MOUNTED	EACH	4.000	X	=		
AR125565	SPLICE CAN	EACH	3.000	X	=		
AR125962	RELOCATE BASE MOUNTED LIGHT	EACH	3.000	X	=		
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1.000	X	=		
AR150520	MOBILIZATION	L.S.	1.000	X	=		
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	6,335.000	X	=		

MIDAMERICA ST. LOUIS  
ST CLAIR

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT NUMBER - SC066

ECMS081 DTGECM03 ECMR003 PAGE 2  
RUN DATE - 01/17/12  
RUN TIME - 111506

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR155540	BY-PRODUCT LIME	TON	383.000	X	=		
AR155612	SOIL PROCESSING-12"	S.Y.	15,195.000	X	=		
AR156510	SILT FENCE	L.F.	1,400.000	X	=		
AR156511	DITCH CHECK	EACH	7.000	X	=		
AR156531	EROSION CONTROL BLANKET	S.Y.	3,000.000	X	=		
AR209609	CRUSHED AGG. BASE COURSE-9"	S.Y.	15,933.000	X	=		
AR209611	CRUSHED AGGREGATE BASE COURSE-11"	S.Y.	469.000	X	=		
AR302611	ASPHALT TREATED PERMEABLE SUBBASE	S.Y.	14,704.000	X	=		
AR302630	ATPS TEST SECTION	EACH	1.000	X	=		
AR401610	BITUMINOUS SURFACE COURSE	TON	152.000	X	=		
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	2,317.000	X	=		
AR403610	BITUMINOUS BASE COURSE	TON	152.000	X	=		
AR501509	9" PCC PAVEMENT	S.Y.	1,075.000	X	=		
AR501516	16" PCC PAVEMENT	S.Y.	13,333.000	X	=		
AR501530	PCC TEST BATCH	EACH	1.000	X	=		

MIDAMERICA ST. LOUIS  
ST CLAIR

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT NUMBER - SC066

ECMS081 DTGECM03 ECMR003 PAGE 3  
RUN DATE - 01/17/12  
RUN TIME - 111506

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR602510	BITUMINOUS PRIME COAT	GAL.	6,151.000 X	=			
AR603510	BITUMINOUS TACK COAT	GAL.	162.000 X	=			
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	1,433.000 X	=			
AR620525	PAVEMENT MARKING-BLACK BORDER	S.F.	1,883.000 X	=			
AR701524	24" RCP, CLASS IV	L.F.	533.000 X	=			
AR701536	36" RCP, CLASS IV	L.F.	407.000 X	=			
AR701900	REMOVE PIPE	L.F.	68.000 X	=			
AR705526	6" PERFORATED UNDERDRAIN W/SOCK	L.F.	1,578.000 X	=			
AR705635	UNDERDRAIN COLLECTION STRUCTURE	EACH	7.000 X	=			
AR705640	UNDERDRAIN CLEANOUT	EACH	8.000 X	=			
AR751540	MANHOLE 4'	EACH	2.000 X	=			
AR752424	PRECAST REINFORCED CONC. FES 24"	EACH	2.000 X	=			
AR752436	PRECAST REINFORCED CONC. FES 36"	EACH	1.000 X	=			
AR752900	REMOVE END SECTION	EACH	2.000 X	=			
AR770508	8" SANITARY SEWER	L.F.	132.000 X	=			

MIDAMERICA ST. LOUIS  
ST CLAIR

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT NUMBER - SC066

ECMS081 DTGECM03 ECMR003 PAGE 4  
RUN DATE - 01/17/12  
RUN TIME - 111506

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR770515	15" SANITARY SEWER	L.F.	341.000 X	=			
AR770704	SANITARY MANHOLE 4'	EACH	1.000 X	=			
AR801971	4' X 20' TRENCH DRAIN	EACH	1.000 X	=			
AR801972	8" VALVE & ACTUATOR	EACH	1.000 X	=			
AR801973	CONTROL SWITCHES	L.S.	1.000 X	=			
AR801974	REMOVE FUMIGATION FACILITY	L.S.	1.000 X	=			
AR801975	REINSTALL FUMIGATION FACILITY	L.S.	1.000 X	=			
AR801976	AIRCRAFT NOSE TETHER ANCHOR	EACH	2.000 X	=			
AR801977	TYPE TC-2-#12, 1-#12 GND, 600V	L.F.	495.000 X	=			
AR801978	TYPE TC-7-#14, 600V	L.F.	495.000 X	=			
AR801979	BASIN SPILLWAY MODIFICATIONS	L.S.	1.000 X	=			
AR901510	SEEDING	ACRE	4.900 X	=			
AR904510	SODDING	S.Y.	410.000 X	=			
AR908510	MULCHING	ACRE	4.400 X	=			
SUBTOTAL BASE				\$			

\*\*\*THE DEPARTMENT RESERVES THE RIGHT TO AWARD THIS CONTRACT ON THE  
\*\*\*BASIS OF ANY OF THE ALTERNATES OR COMBINATION THEREOF.

MIDAMERICA ST. LOUIS  
ST CLAIR

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT NUMBER - SC066

ECMS081 DTGECM03 ECMR003 PAGE 5  
RUN DATE - 01/17/12  
RUN TIME - 111506

\*\*\*\*\* ALT 1 \*\*\*\*\*

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AS108108	1/C #8 5 KV UG CABLE	L.F.	176.000 X			=	
AS108706	1/C #6 COUNTERPOISE	L.F.	979.000 X			=	
AS110202	2" PVC DUCT, DIRECT BURY	L.F.	80.000 X			=	
AS110501	1-WAY CONC. ENCASED DUCT	L.F.	145.000 X			=	
AS110502	2-WAY CONCRETE ENCASED DUCT	L.F.	379.000 X			=	
AS110610	ELECTRICAL HANDHOLE	EACH	1.000 X			=	
AS125415	MITL-BASE MOUNTED	EACH	1.000 X			=	
AS125565	SPLICE CAN	EACH	2.000 X			=	
AS152410	UNCLASSIFIED EXCAVATION	C.Y.	3,052.000 X			=	
AS155540	BY-PRODUCT LIME	TON	144.000 X			=	
AS155612	SOIL PROCESSING-12"	S.Y.	5,713.000 X			=	
AS156510	SILT FENCE	L.F.	200.000 X			=	
AS209609	CRUSHED AGG. BASE COURSE-9"	S.Y.	5,534.000 X			=	
AS209611	CRUSHED AGGREGATE BASE COURSE-11"	S.Y.	116.000 X			=	
AS302611	ASPHALT TREATED PERMEABLE SUBBASE	S.Y.	5,764.000 X			=	

MIDAMERICA ST. LOUIS  
ST CLAIR

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT NUMBER - SC066

ECMS081 DTGECM03 ECMR003 PAGE 6  
RUN DATE - 01/17/12  
RUN TIME - 111506

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AS401650	BITUMINOUS PAVEMENT MILLING	S.Y.	48.000 X	=			
AS501509	9" PCC PAVEMENT	S.Y.	1,875.000 X	=			
AS501516	16" PCC PAVEMENT	S.Y.	3,556.000 X	=			
AS602510	BITUMINOUS PRIME COAT	GAL.	2,120.000 X	=			
AS620520	PAVEMENT MARKING-WATERBORNE	S.F.	258.000 X	=			
AS620525	PAVEMENT MARKING-BLACK BORDER	S.F.	299.000 X	=			
AS705526	6" PERFORATED UNDERDRAIN W/SOCK	L.F.	414.000 X	=			
AS705635	UNDERDRAIN COLLECTION STRUCTURE	EACH	1.000 X	=			
AS705640	UNDERDRAIN CLEANOUT	EACH	2.000 X	=			
AS801976	AIRCRAFT NOSE TETHER ANCHOR	EACH	2.000 X	=			
AS901510	SEEDING	ACRE	0.900 X	=			
AS904510	SODDING	S.Y.	248.000 X	=			
AS908510	MULCHING	ACRE	0.900 X	=			

SUBTOTAL ALT 1 \$ 

--	--

MIDAMERICA ST. LOUIS  
ST CLAIR

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT NUMBER - SC066

ECMS081 DTGECM03 ECMR003 PAGE 7  
RUN DATE - 01/17/12  
RUN TIME - 111506  
CONTRACT - SC066

SUMMARY OF TOTAL ALTERNATES		
	DOLLARS	CTS
TOTAL BASE \$		
TOTAL ALT 1 \$		

NOTE:

1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
3. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.