	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0004 80% FED 20% STATE URBAN
	35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	184	184
	35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	147	147
	35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	37	37
	40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	421	421
	40600982	HOT MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	21	21
*	40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	105	105
	40600370	LONGITUDINAL JOINT SEALANT	FOOT	325	325
*	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	184	184
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	132	132
*	42400800	DETECTABLE WARNINGS	SQ FT	13	13
	44000100	PAVEMENT REMOVAL	SQ YD	143	143
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	735	735
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	162	162
	44000400	GUTTER REMOVAL	FOOT	34	34
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	411	411
	44000600	SIDEWALK REMOVAL	SQ FT	151	151
	44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	124	124
	48101498	AGGREGATE SHOULDERS, TYPE B 4"	SQ YD	81	81
	48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	130	130
	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1
	50200100	STRUCTURE EXCAVATION	CU YD	66	66
	50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	39	39
	50300225	CONCRETE STRUCTURES	CU YD	86.9	86.9
	~~50300255~~	~~CONCRETE SUPERSTRUCTURE~~	~~CU YD~~	~~86.9~~	~~86.9~~
	50300285	FORM LINER TEXTURED SURFACE	SQ FT	1,475	1,475
	50500505	STUD SHEAR CONNECTORS	EACH	256	256

1 REVISED SHEET 1/6/2023

USER: sjohnson
MODEL: Default
FILE NAME: P:\02_209_004_IDOT PTB 190_14 Phase II Var-VarDesign\WO 2 62H02\CADD\CADD Sheets\D162H02-sht-soq-02.dgn

PLOT DRIVER = pdfNOLAYERSbw.pltcfg	DESIGNED - WL	REVISED -	
PEN TABLE = D162H02-PreFinal.tbl	DRAWN - SVJ	REVISED -	
PLOT SCALE = 2.0000 ' / in.	CHECKED - PJM	REVISED -	
PLOT DATE = 10/20/2022 2:26:03 PM	DATE - 09/22/2022	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: 2.0000 ' / in. | SHEET 2 OF 4 SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3887	2018-042-CR	KANE	53	5

CONTRACT NO. 62H02

ILLINOIS | FED. AID PROJECT STP-BKRQ(921)

REV-SEP