



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 10, 2023

SUBJECT: Shared Use Path
Section 17-00178-00-BT (Dixon)
Lee County
Contract No. 85700
Item 121
January 20, 2023 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices**
- 2. Revised Plan Sheets 6, 7, 8, 9, 27, 84, 86, & 89**
- 3. Revised Special Provision Index**
- 4. Added page 8A to the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

INDEX OF SPECIAL PROVISIONS

Page:	Special Provisions:
1	LOCATION OF PROJECT
1	DESCRIPTION OF IMPROVEMENTS
1	J.U.L.I.E.
1	PERMANENT SHEET PILING
1	SEGMENTAL CONCRETE BLOCK WALL
2	ENGINEERED BARRIER
2	ELECTRICAL SERVICE INSTALLATION
2	SHREDDED BARK MULCH 3”
3	CLEARING AND GRUBBING
3	COMMUNICATIONS CABINET AND EQUIPMENT
3	ADJUST MONITORING WELLS
3	WASHOUT BASIN
3	TRASH RECEPTACLES
3	POWER PEDESTALS
4	LIGHT POLE, SPECIAL 12’
4	LUMINAIRE, LED, SPECIAL
4	CONCRETE REMOVAL (SPECIAL)
4	BICYCLE RAILING, SPECIAL
4	MEMBRANE WATERPROOFING (SPECIAL)
5	TRAFFIC CONTROL AND PROTECTION (SPECIAL)
6	MAINTENANCE OF TRAFFIC
7	JUNCTION BOX (SPECIAL)
7	LIGHTING UNIT COMPLETE, SPECIAL
7	LIGHT POLE FOUNDATION, SPECIAL
8	BENCHES
8	WOOD POST AND RAIL FENCE
8	BOARDWALK STRUCTURE
8	EMERGENCY CALL BOXES
8A	MOWING (SPECIAL)
9	REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES
11	BDE 2342 STORM WATER POLLUTION PREVENTION PLAN
19	LR107-4 INSURANCE
20	LR702 CONSTRUCTION AND MAINTENANCE SIGNS
21	LR1020-2 LOCAL QUALITY ASSURANCE / QUALITY MANAGEMENT QC/QA
22	IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING

Local Public Agency

County

Section Number

City of Dixon

Lee

17-00178-00-BT

X2503110 - MOWING (SPECIAL)

This work shall consist of mowing all grassed, turfed, and/or temporary seeded areas within the project right-of-way limit so as not to allow the growth and establishment of vegetation or floral resources. The project shall be mowed from March 15th through October 14th of any given year for the length of construction so as not to allow the growth and establishment of vegetation or floral resources.

Mower decks shall be set at a height that does not cause scalping and soil disturbance. It is recommended that areas which are not currently mowed and maintained, be mowed at a deck height of 6 inches, unless the vegetation is shorter such that this deck setting would not be feasible. Areas which are currently mowed and maintained shall be mowed and maintained at the current height and deck settings. This work shall include all labor, material, and equipment necessary to complete the work described above.

Each mowing occurrence will be paid for separately.

Disturbed areas shall be reseeded with a Class 4 and 5 A or B seed mixture in accordance with Section 250 of IDOT's Standard Specifications for Road and Bridge Construction.

This work shall be paid for at the contract unit price per ACRE for MOWING (SPECIAL)