

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1349	3197 (A&B) RS	COOK	33	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

7060 CONTRACT # 60721

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000 100%STATE DEVON AVE				CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000 100%STATE DEVON AVE	Y060 URBAN 100%PARK RIDGE			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	50	50				60251730	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	17	17				
40600300	AGGREGATE (PRIME COAT)	TON	250	250				60255500	MANHOLES TO BE ADJUSTED	EACH	15		15			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	6.5	6.5				60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	12	12				
X4060420	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIXTURE D, N10	TON	5440	5440				60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	94	75	19			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	9	9				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	700	700				60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	76	76				
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	495	495				60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	400	400				
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	175	175				67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1450	1450				67100100	MOBILIZATION	L SUM	1	1				
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	1800	1800				70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
44000110	BITUMINOUS REMOVAL OVER PATCHES 2 1/2"	SQ YD	3441	3441				70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	175	175				70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
44000600	SIDEWALK REMOVAL	SQ FT	1450	1450				70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10375	10375				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	6250	6250				70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	292	292				
44003100	MEDIAN REMOVAL	SQ FT	400	400				70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	17190	17190				
44200990	CLASS B PATCHES, TYPE I, 12 INCH	SQ YD	11	11				70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1290	1290				
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	69	69				70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	650	650				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	4200	4200				70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	280	280				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	250	250				70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	292	292				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	400	400				70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	300	300				
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	36	36				* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	292	292				
44213200	SAW CUTS	FOOT	48	48				* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	17190	17190				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	95	95				* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1290	1290				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	190	190												
55039700	STORM SEWERS TO BE CLEANED	FOOT	800	800												
60250200	CATCH BASINS TO BE ADJUSTED	EACH	16	16												
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	6	6												

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES