

SUMMARY OF QUANTITIES

62693

CODE NO.	ITEM	UNIT	QUANTITY	URBAN ROADWAY		RETAINING WALLS										CORNER GARDENS	SIGNING	SAFETY	LIGHTING	SURVEILLANCE	SIGNALS	
				90% FED. / 10% STATE	100% STATE	IDOT	J000	Y007	Y007	Y007	Y007	Y007	Y007	Y007	Y007							Y007
				J000-2A	J000	Y007	Y007	Y007	Y007	Y007	Y007	Y007	Y007	Y007	Y007							
20101000	TEMPORARY FENCE	FOOT	204		204																	
20200100	EARTH EXCAVATION	CU YD	18,885	18,885																		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	3,450	3,450																		
20700220	POROUS GRANULAR EMBANKMENT	CU YD	17,865			466	6,142	2,856	46	3,561	293	4,470		31								
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	1,001				176	220		370		230		5								
20800150	TRENCH BACKFILL	CU YD	3,450	529	2,921																	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	9,011	9,011																		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	13,506	13,484										22								
21101630	TOPSOIL FURNISH AND PLACE, 8"	SO YD	6,915	6,915																		
21101815	COMPOST FURNISH AND PLACE, 4"	SO YD	6,915	6,915																		
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	598		598																	
25000210	SEEDING, CLASS 2A	ACRE	3.50	3.50																		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	316	316																		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	316	316																		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	316	316																		
25000750	MOWING	ACRE	4.25	4.25																		
25100401	EXCELSIOR BLANKET, SPECIAL	SO YD	22											22								
25100630	EROSION CONTROL BLANKET	SO YD	20,401	20,401																		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	422	422																		
28000400	PERIMETER EROSION BARRIER	FOOT	6,320	6,320																		
28000510	INLET FILTERS	EACH	187	73	114																	
31101600	SUB-BASE GRANULAR MATERIAL, TYPE B, 8"	SO YD	26,893		26,865									28								
31101860	SUB-BASE GRANULAR MATERIAL, TYPE B, 24"	SO YD	9,011	9,011																		
31200100	STABILIZED SUB-BASE, 4"	SO YD	4,930	4,930																		
35101600	AGGREGATE BASE COURSE, TYPE B, 4"	SO YD	472	472																		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8.7	8.7																		
40600300	AGGREGATE (PRIME COAT)	TON	19	19																		
40600895	CONSTRUCTING TEST STRIP	EACH	3	3																		
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD	24,684		24,684																	
42000521	PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED)	SO YD	3,535	3,535																		

⊙⊙ Y102
 ⊙ NON-PARTICIPATING

* DENOTES SPECIALTY ITEMS



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
 63rd ST TO 59th ST (FRONTAGE ROAD & RAMPS)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: AMM
 DATE: October 29, 2004 CHECKED BY: RMG

11/29/2004 9:23:51 AM