F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2021-922PT.1-AC	COOK	460	10
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

62693

SUMMARY OF QUANTITIES

					90% FED. 10% STATE	100% STATE	90% FEDERAL / 10% STATE								100% STATE	90% FED./10% STATE				
					URBAN ROADWAY		RETAINING WALLS								CORNER GARDENS	SIGNING	SAFETY	LIGHTING	SURVEILLANCE	SIGNALS
				URBAN	IDOT		016-W882	016-W886	016-W894 016-W964	016-W901	016-W903 016-W906	016-W907	016-W887 016-W965	016-WWRR						
CODE NO.	ITEM	UNIT	QUANTITY		J000-2A	J000	Y007	Y007	Y007	Y007	Y007	Y007	Y007	Y007	Y007	Y002-1C	SFTY-3N	Y030-1E	Y032-1F	Y031-1F
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	4	4																
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	7	7																
67100100	MOBILIZATION	L SUM	1	1																
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1		1															
70300240	TEMPORARY PAVEMENT MARKING, LINE 6"	FOOT	12,330	7,070	5,260															
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	582		582															
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	20,287		20,287															
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	521		521															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	8,294		8,294															
70400100	TEMPORARY CONCRETE BARRIER	FOOT	10,820	5,560	5,260															
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,510	1,510																
72000200	SIGN PANEL-TYPE 2	SQ FT	20													20				
72000300	SIGN PANEL-TYPE 3	SQ FT	438													438				
72100100	SIGN PANEL OVERLAY	SQ FT	162													162				
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	184													184				
72400720	RELOCATE SIGN PANEL - TYPE 2	SQ FT	68													68				
72700100	STRUCTURAL STEEL SIGN SUPPORT-BREAKAWAY	POUND	543													543				
72900200	METAL POST - TYPE B	FOOT	29													29				
73000100	WOOD SIGN SUPPORT	FOOT	130													130				
73000105	WOOD SIGN SUPPORT (SPECIAL)	FOOT	17																17	
73302210	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (36" X 7'-0")	FOOT	68													68				
* 73305000	OVERHEAD SIGN STRUCTURE - WALKWAY	FOOT	32													32				
73400100	CONCRETE FOUNDATIONS	CU YD	2													2				
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	16													16				
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	2													2				
73700100	REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	4													4				
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	4													4				
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	2													2				
78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	3,273	3,273																
78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	244	244																

*SPECIALTY ITEMS

* DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63rd ST TO 59th ST (FRONTAGE ROAD & RAMPS)

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: October 29, 2004
DRAWN BY: AMM
CHECKED BY: RMG

CTE ENGINEERS
CONSOER TOWNSEND ENVIRODYNE ENGINEERS, INC.
303 EAST WACKER DRIVE, SUITE 600
CHICAGO ILLINOIS 60601-5202. PHONE: (312) 938-0300

m:\04068\civil\4c-cntr\9c\sht\general\sq09c0052a.sht
11/29/2004 9:23:53 AM