


ROADWAY ITEMS SCHEDULE

STATION TO STATION	SHEET	CDOT					RAMPS AND MAINLINE										
		SUB-BASE GRANULAR MATERIAL, TYPE B 8"	PORTLAND CEMENT CONC. PAVEMENT, 10" (JOINTED)	PORTLAND CEMENT CONC. SIDEWALK, 5"	SAND CUSHION, 3"	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SUB-BASE GRANULAR MATERIAL, TYPE B, 24"	STABILIZED SUB-BASE, 4"	PORTLAND CEMENT CONC. PAVEMENT, 11" (JOINTED)	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONC. PAVEMENT, 14"	PORTLAND CEMENT CONC. SHOULDERS, 11"	WHITWASHING FOR P.C.C. PAVEMENT	TEMPORARY PAVEMENT (INTERSTATE)	PORTLAND CEMENT CONC. SHOULDERS, 14"	STABILIZED SUB-BASE, 6"	PAVEMENT REINFORCEMENT, 14"	
WENTWORTH AVENUE		SO YD	SO YD	SO FT	CU YD	SO YD	SO YD	SO YD	SO YD	SO YD	SO YD	SO YD	SO YD	SO YD	SO YD	SO YD	SO YD
99+99.22 TO 103+00.00	1	1,146	1,040	310	3	0	0	0	0	0	0	0	0	0	0	0	0
103+00.00 TO 108+00.00	2	2,418	2,252	0	0	0	0	0	0	0	0	0	301	0	0	0	0
108+00.00 TO 113+00.00	3	2,129	1,955	0	0	701	701	878	655	0	0	878	500	0	0	0	0
113+00.00 TO 118+00.00	4	1,907	1,734	0	0	1,112	1,112	356	268	517	0	1,181	714	64	825	517	0
118+00.00 TO 123+00.00	5	1,843	1,667	0	0	1,301	1,301	136	96	786	12	1,301	1,718	8	1,165	786	0
123+00.00 TO 128+00.00	6	2,160	1,947	0	0	1,007	1,007	1,007	713	0	86	1,007	765	0	0	0	0
128+00.00 TO 133+00.00	7	2,290	2,151	75	1	0	0	0	0	0	0	0	417	0	0	0	0
SUB-TOTALS		13,893	12,746	385	4	4,121	4,121	2,377	1,732	1,303	98	4,367	4,415	72	1,990	1,303	0
WELLS STREET																	
506+92.81 TO 511+50.00	8	2,767	2,577	325	3	141	141	141	103	0	8	141	0	0	0	0	0
511+50.00 TO 516+50.00	9	1,795	1,618	0	0	1,512	1,512	1,094	775	256	97	1,512	652	78	418	256	0
516+50.00 TO 521+75.00	10	1,993	1,807	0	0	1,493	1,493	0	0	1,008	0	1,493	609	93	1,493	1,008	0
521+75.00 TO 526+75.00	11	1,808	1,632	0	0	1,281	1,281	855	605	291	75	1,281	679	0	426	291	0
526+75.00 TO 531+75.00	12	2,282	2,098	0	0	463	463	463	320	0	33	463	502	0	0	0	0
531+75.00 TO 536+75.00	13	2,327	2,206	322	3	0	0	0	0	0	0	0	338	0	0	0	0
SUB-TOTALS		12,972	11,938	647	6	4,890	4,890	2,553	1,803	1,555	213	4,890	2,780	171	2,337	1,555	0
TOTALS		26,865	24,684	1,032	10	9,011	9,011	4,930	3,535	2,858	311	9,257	7,195	243	4,327	2,858	0



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
 63rd ST TO 59th ST (FRONTAGE ROAD & RAMPS)

SCHEDULE OF QUANTITIES

SCALE: NONE  
 DATE: October 29, 2004

DRAWN BY: AMM  
 CHECKED BY: RMG