

MAINTENANCE OF TRAFFIC ITEMS

F.A.I. RT.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2021-922PT.1-AC	COOK	460	64
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	62693	

		MAINLINE (J000)																	
		TEMPORARY PAVEMENT MARKING, LINE 6"	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	EPOXY PAVEMENT MARKING - LINE 4"	EPOXY PAVEMENT MARKING - LINE 5"	EPOXY PAVEMENT MARKING - LINE 8"	EPOXY PAVEMENT MARKING - LINE 12"	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	PAVEMENT MARKING REMOVAL	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CHANGEABLE MESSAGE SIGN	WORK ZONE PUBLIC INFORMATION SIGNS	IMPACT ATTENUATOR REMOVAL	IMPACT ATTENUATORS (NON-REDIRECTIVE) TEST LEVEL 3	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	
		FOOT	FOOT	FOOT	SO FT	FOOT	FOOT	FOOT	FOOT	EACH	SO FT	L SUM	CAL DAY	CAL MONTH	EACH	EACH	EACH	EACH	
STAGE 1 - NORTHBOUND																			
	NB 4426+00 - 4435+50	1660	1370	290	109	2531	431	247	0	122	588	*	*	*	*	0	0	1	
	NB 4435+50 - 4449+55	1400	1400	0	36	2576	355	1452	248	56	1806	*	*	*	*	1	1	0	
	SUBTOTAL	3060	2770	290	146	5107	786	1699	248	178	2394	*	*	*	*	1	1	1	
STAGE 1 - SOUTHBOUND																			
	SB 3430+00 - 3435+50	2630	1410	1220	73	880	108	328	0	162	244	*	*	*	*	0	0	0	
	SB 3435+50 - 3449+30	1380	1380	0	73	2393	463	980	114	56	2231	*	*	*	*	0	0	0	
	SUBTOTAL	4010	2790	1220	146	3273	571	1308	114	218	2475	*	*	*	*	0	0	0	
STAGE 2 - NORTHBOUND																			
	NB 4426+00 - 4435+50	0	0	0	0	0	0	0	0	0	2900	*	*	*	*	0	0	0	
	NB 4435+50 - 4449+55	0	0	0	0	0	0	0	0	0	0	*	*	*	*	0	0	0	
	SUBTOTAL	0	0	0	0	0	0	0	0	0	2900	*	*	*	*	0	0	0	
STAGE 2 - SOUTHBOUND																			
	SB 3430+00 - 3435+50	0	0	0	0	0	0	0	0	0	2153	*	*	*	*	0	0	0	
	SB 3435+50 - 3449+30	0	0	0	0	0	0	0	0	0	0	*	*	*	*	0	0	0	
	SUBTOTAL	0	0	0	0	0	0	0	0	0	2153	*	*	*	*	0	0	0	
ADDITIONAL CONTRACT QUANTITIES		---	---	---	---	---	---	---	---	---	---	1	206	23	4	---	---	---	
MAINLINE TOTAL		7070	5560	1510	292	8380	1357	3007	362	396	9922	1	206	23	4	1	1	1	

* SEE ADDITIONAL CONTRACT QUANTITIES

		FRONTAGE (I000)														
		PAVEMENT REMOVAL	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	TEMPORARY PAVEMENT MARKING, LINE 6"	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	PAVEMENT MARKING TAPE, TYPE III - 4"	PAVEMENT MARKING TAPE, TYPE III - 24"	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY CONCRETE BARRIER	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	PAVEMENT MARKING REMOVAL	TEMPORARY INFORMATION SIGNING	CHANGEABLE MESSAGE SIGN	TEMPORARY PAVEMENT, 10" (SPECIAL)	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	
		SO YD	L SUM	FOOT	SO FT	FOOT	FOOT	SO FT	FOOT	EACH	SO FT	SO FT	CAL MO	SO YD	EACH	
PRESTAGE - NB WENTWORTH																
	NB 102+00 - 117+50	0	*	480	0.0	0	0	0	480	20	0	0	*	0	1	
	NB 117+50 - 133+00	0	*	950	0.0	0	0	0	950	38	0	0	*	0	0	
	SUBTOTAL	0	*	1430	0	0	0	0	1430	58	0	0	*	0	1	
STAGE 1 - NB WENTWORTH																
	NB 102+00 - 117+50	0	*	810	72.8	3392	59	1259	810	33	644	30.25	*	172	0	
	NB 117+50 - 133+00	0	*	420	109.2	3480	58	1422	420	17	374	30.25	*	161	0	
	SUBTOTAL	0	*	1230	182	6872	117	2681	1230	50	1018	61	*	333	0	
STAGE 1 - SB WELLS																
	SB 505+50 - 521+00	0	*	1290	109.2	2089	61	929	1290	52	190	30.25	*	0	0	
	SB 521+00 - 536+50	0	*	1310	109.2	1542	83	754	1310	53	370	30.25	*	0	0	
	SUBTOTAL	0	*	2600	218	3631	144	1683	2600	105	560	60.5	*	0	0	
STAGE 2 - NB WENTWORTH																
	NB 102+00 - 117+50	172	*	0	72.8	3403	57	1214	0	0	0	30.25	*	0	0	
	NB 117+50 - 133+00	161	*	0	0.0	3300	66	1340	0	0	0	30.25	*	0	0	
	SUBTOTAL	333	*	0	73	6703	123	2554	0	0	0	60.5	*	0	0	
STAGE 2 - SB WELLS																
	SB 505+50 - 521+00	0	*	0	109.2	1870	59	742	0	0	0	30.25	*	0	0	
	SB 521+00 - 536+50	0	*	0	0.0	1211	78	634	0	0	0	30.25	*	0	0	
	SUBTOTAL	0	*	0	109	3081	137	1376	0	0	0	60.5	*	0	0	
ADDITIONAL CONTRACT QUANTITIES		---	1	---	---	---	---	---	---	---	---	51.4	16	---	---	
FRONTAGE TOTAL		333	1	5260	582	20287	521	8294	5260	213	1578	294	16	333	1	

* SEE ADDITIONAL CONTRACT QUANTITIES



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63rd ST TO 59th ST (FRONTAGE ROAD & RAMPS)

SCHEDULE OF QUANTITIES

SCALE: NONE
DATE: October 29, 2004

DRAWN BY: SWANG
CHECKED BY: RMG

11/24/2004 02:03:04 PM I:\P\40468\CHITV\FE-CITP90\SHAM01-Sigging\MT 050002A.DWG