

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2689	(3185&3186) RS-2	COOK	19	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
C62698				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN 1000-2A 100% STATE					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	36	36					
40600300	AGGREGATE (PRIME COAT)	TON	174	174					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	4	4					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	197	197					
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	475	475					
42001300	PROTECTIVE COAT	SQ YD	418	418					
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	15470	15470					
44000124	BITUMINOUS REMOVAL OVER PATCHES 6"	SQ YD	1415	1415					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	695	695					
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	4	4					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	444	444					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	157	157					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	497	497					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	2	2					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	55	55					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	12	12					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	40	40					
60404940	FRAMES AND GRATES, TYPE 23	EACH	52	52					
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	8	8					
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	23	23					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	4					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10775	10775					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	944	944					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN 1000-2A 100% STATE					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	21064	21064					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6578	6578					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1054	1054					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	408	408					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	472	472					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10533	10533					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3289	3289					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	527	527					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	204	204					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	769	769					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	769	769					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1055	1055					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	104	104					
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	3075	3075					
X4066546	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	1516	1516					
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	1834	1834					
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	36612	36612					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	15	15					

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
WOLF ROAD
IL. 38 (Roosevelt Rd.) TO 22nd Street (Cermak Rd.)
PLOT DATE: 10/26/2004

: 08:44:17 10/26/2004

10/26/2004
08:44:17 10/26/2004