

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		ROADWAY 100% STATE I000-2A						CODE NO	ITEM		UNIT	ROADWAY 100% STATE I000-2A				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	170	170														
* 81016400	CONDUIT IN TRENCH, 1 1/4" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	30		30													
* 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	30		30													
* 87900205	DRILL EXISTING HEAVY DUTY HANDHOLE	EACH	1		1													
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	400		400													
X0301271	REMOVE EXISTING UNDERDRAINS	FOOT	900	900														
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	68	68														
* X0322300	ELECTRIC CABLE IN CONDUIT NO. 18 4/C, TWISTED, SHIELDED	FOOT	750		750													
* X0322440	DIGITAL LOOP DETECTOR SENSOR UNIT (2 CHANNEL)	EACH	1		1													
* X0322442	TONE EQUIPMENT - 3 FREQUENCY RECEIVER PROGRAMMABLE	EACH	1		1													
* X0322443	TONE EQUIPMENT - 3 FREQUENCY TRANSMITTER PROGRAMMABLE	EACH	1		1													
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	2	2														
X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	3	3														
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	321	321														
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	321	321														
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1														
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	30	30														
* X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	6		6													
* X8850102	INDUCTION LOOP	FOOT	34		34													
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1														
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	2	2														
△ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1														

\* SPECIALTY ITEMS  
 △ SFTY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 I-90 @ I-190 RAMP