

# SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	37R-2	OGLE	389	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	SIGNALS		RESURF	SIDEWALK	UTIL. AD	WATER	CONTRACT #64157
				80 % FED 20 % STAT J000-2A	10% STATE 10% CITY Y031-1F	100% CIT 1000	25% STAT 75% CITY SFTY-1B	50% ST. 50% CIT Y060	38 % ST. 62% CITY Y060	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	240	240						
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1						
* 78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	302	302						
78200405	GUARDRAIL MARKERS	EACH	12	12						
80501000	SERVICE INSTALLATION (SPECIAL)	EACH	2		2					
81306500	REMOVE EXISTING JUNCTION BOX	EACH	1		1					
81400400	CONCRETE HANDHOLE	EACH	8		8					
81400600	CONCRETE DOUBLE HANDHOLE	EACH	2		2					
82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	8		8					
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2		2					
85900100	TRANSCEIVER	EACH	3		3					
86000100	MASTER CONTROLLER	EACH	1		1					
87900200	DRILL EXISTING HANDHOLE	EACH	1		1					
88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	17		17					
88500100	INDUCTIVE LOOP DETECTOR	EACH	13		13					
88800100	PEDESTRIAN PUSH-BUTTON	EACH	12		12					
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1					
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1		1					
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1					
89502380	REMOVE EXISTING HANDHOLE	EACH	4		4					
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	6		6					
A2001714	TREE, ACER SACCHARUM (SUGAR MAPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	10	10						
A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	7	7						
A2007820	TREE, TILIA AMERICANA (AMERICAN LINDEN/ BASSWOOD), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	10	10						
B2000562	TREE, AMELANCHIER CANADENSIS (SHADBLOW SERVICEBERRY), 4' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	10	10						
B2004114	TREE, MALUS PRAIRIFIRE (PRAIRIFIRE CRABAPPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	10	10						
B2005014	TREE, MALUS SNOWDRIFT (SNOWDRIFT CRABAPPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	10	10						
C2004436	SHRUB, LONICERA XYLOSTEUM CLAVEYI (CLAVEY'S DWARF HONEYSUCKLE), 3' HEIGHT BALLED & BURLAPPED	EACH	50	50						
C2012936	SHRUB, <sup>VIBURNUM</sup> TRILOBUM BAILEY COMPACT (BAILEY COMPACT AMERICAN CRANBERRY), 3' HEIGHT BALLED & BURLAPPED	EACH	50	50						
M2010110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	84	84						
M2010210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	477	477						
M2010500	TREE REMOVAL, HECTARES	HA	0.161	0.161						
M2011000	TEMPORARY FENCE	METER	480	480						
M2022010	EARTH EXCAVATION	CU METER	19428	19428						
M2080150	TRENCH BACKFILL	CU METER	1197	1197						

SUMMARY OF QUANTITIES