

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	37R-2	OGLE	389	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT #64157				

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	80 % FED 20 % STAT J000-2A	80 % FED 10% STATE 10% CITY Y031-1F	RESURF 100% CIT 1000	SIDEWALK 25% STAT 75% CITY SFTY-1B	UTIL. AD 50% ST. 50% CIT Y060	WATER 38% ST. 62% CITY Y060
M2113100	TOPSOIL FURNISH AND PLACE, 100 MM	SQ METER	26626	26626					
M2500310	SEEDING, CLASS 4	HA	0.284	0.284					
M2500400	NITROGEN FERTILIZER NUTRIENTS	KG	266	266					
M2500500	PHOSPHOROUS FERTILIZER NUTRIENT	KG	266	266					
M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	266	266					
M2500750	MOWING	HA	5.320	5.320					
M2501830	SEEDING, CLASS 6 (MODIFIED)	HA	0.633	0.633					
M2510115	MULCH, METHOD 2	HA	1.834	1.834					
M2510630	EROSION CONTROL BLANKET	SQ METER	1274	1274					
M2520100	SODDING	SQ METER	17477	17477					
M2520200	SUPPLEMENTAL WATERING	UNIT	784	784					
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	562	562					
M2800400	PERIMETER EROSION BARRIER	METER	48	48					
M2810105	STONE RIPRAP, CLASS A3	SQ METER	185	185					
M2810107	STONE RIPRAP, CLASS A4	SQ METER	10	10					
M2820100	FILTER FABRIC FOR USE WITH RIPRAP	SQ METER	195	195					
M3110300	SUB-BASE GRANULAR MATERIAL, TYPE A 300MM	SQ METER	42311	42311					
M3511010	AGGREGATE BASE COURSE, TYPE B	M TON	4686	4686					
M4012150	AGGREGATE SHOULDERS, TYPE B 150mm	SQ METER	29	29					
M4060200	BITUMINOUS MATERIALS (PRIME COAT)	M TON	34.52	34.52					
M4060990	TEMPORARY RAMP	SQ METER	888	888					
M4080300	AGGREGATE (PRIME COAT)	M TON	34.72	34.72					
M4202245	PORTLAND CEMENT CONCRETE PAVEMENT 240MM (JOINTED)	SQ METER	29289	29289					
M4230175	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 175MM	SQ METER	3524	3524					
M4240125	PORTLAND CEMENT CONCRETE SIDEWALK, 125MM	SQ METER	2051	1239			812		
M4400000	BITUMINOUS SURFACE REMOVAL	SQ METER	983			983			
M4400025	BITUMINOUS SURFACE REMOVAL (25.0MM)	SQ METER	496	496					
M4402000	PAVEMENT REMOVAL	SQ METER	24470	24470					
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ METER	9143	9143					
M4402030	GUTTER REMOVAL	METER	447	447					
M4402040	COMBINATION CURB & GUTTER REMOVAL	METER	2926	2926					
M4402050	SIDEWALK REMOVAL	SQ METER	1351	1351					
M4402090	BITUMINOUS CONCRETE CURB & GUTTER REMOVAL	METER	207	207					
M4402220	BITUMINOUS SHOULDER REMOVAL	SQ METER	3091	3091					

Tue Nov 09 08:34:55 2004
c:\projects\m200706\schedule.dgn