

# SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	37R-2	OGLE	389	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT #64157				

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	80 % FED 20 % STAT J000-2A	80 % FED 10% STATE 10% CITY Y031-1F	RESURF 100% CIT I000	SIDEWALK	UTIL. AD	WATER	25% STAT	50% ST	38% ST
										75% CITY SFTY-1B	50% CIT Y060	62% CITY Y060
M7030580	PAVEMENT MARKING TAPE, TYPE-3, 600 MM	METER	175	175								
M7030620	TEMPORARY PAINT PAVEMENT MARKING LINE, 100MM	METER	7224	7224								
M7030650	TEMPORARY PAINT PAVEMENT MARKING LINE, 600MM	METER	8.4	8.4								
M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ METER	993.6	993.6								
* M7200200	SIGN PANEL-TYPE 2	SQ METER	11		11							
* M7800600	EPOXY PAVEMENT MARKING - LETTERS & SYMBOLS	SQ METER	109	109								
* M7800605	EPOXY PAVEMENT MARKING - LINE 100MM	METER	4289	4289								
* M7800615	EPOXY PAVEMENT MARKING - LINE 150MM	METER	551	551								
* M7800620	EPOXY PAVEMENT MARKING - LINE 200MM	METER	348	348								
* M7800625	EPOXY PAVEMENT MARKING - LINE 300MM	METER	53	53								
* M7800640	EPOXY PAVEMENT MARKING - LINE 600MM	METER	192	192								
M7830100	PAVEMENT MARKING REMOVAL	SQ METER	936	936								
* M8100230	CONDUIT IN TRENCH, 25MM DIA., PVC	METER	95		95							
* M8100240	CONDUIT IN TRENCH, 30MM DIA., PVC	METER	435		435							
* M8100250	CONDUIT IN TRENCH, 40MM DIA., PVC	METER	29		29							
* M8100270	CONDUIT IN TRENCH, 65MM DIA., PVC	METER	42		42							
* M8100280	CONDUIT IN TRENCH, 75MM DIA., PVC	METER	64		64							
* M8100300	CONDUIT IN TRENCH, 100MM DIA., PVC	METER	73		73							
* M8101470	CONDUIT PUSHED, 75MM DIA., PVC	METER	43		43							
* M8101490	CONDUIT PUSHED, 100MM DIA., PVC	METER	44		44							
M8150200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	737		737							
* M8170020	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	METER	1227		1227							
* M8731210	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C	METER	637		637							
* M8731220	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	METER	126		126							
* M8731240	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	METER	844		844							
* M8731250	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	METER	772		772							
* M8731510	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3-PAIR	METER	366		366							
* M8731710	ELECTRIC CABLE IN CONDUIT, COMMUNICATION, NO. 18 6 PAIR	METER	774		774							
* M8731810	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3C	METER	38		38							
* M8770755	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 10.97 METER	EACH	1		1							
* M8770760	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 11.58 METER	EACH	1		1							
* M8770765	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 12.19 METER	EACH	1		1							
* M8770770	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 12.80 METER	EACH	1		1							
* M8770779	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 14.63 METER	EACH	2		2							

\* SPECIALTY ITEMS

SUMMARY OF QUANTITIES