

GENERAL NOTES

ROUTE NO.	SEC.	COUNTY	TOTAL SHEETS	SHEET NO.
FAP 742	37R-2	Ogle	389	12
FED ROAD DIST. NO.	ILLINOIS	PROJECT		

64157

Program #5
(Arch. Size)
Enlarge
200%
Enlarge 107%

- * The Resident Engineer or Contractor will inform Cacciatore's approximately two weeks in advance for any work to be done to the entrances or the parking lot.
 - * No State or Contractor vehicles will be allowed to park in Cacciatore's lot.
 - * The trees in the planters (excluding the corner planters to be removed) shall not be disturbed.
 - * The tree within the planter at Sta. 17+028 offset Lt. will be saved.
 - * Please note: A portion of Cacciatore's sprinkler system is within roadway right-of-way.
 - * The Resident Engineer shall contact the property owner two weeks in advance of any construction operation within this sprinkler system area. The Contractor shall use extreme caution in this area not to disturb or destroy the system.
 - * The sign in the southwest corner of the Cacciatore's lot will be relocated within the easement area by the property owner during construction. The Contractor shall use extreme caution in this area not to disturb or damage this sign. If damaged by the Contractor, the Contractor shall repair or replace the sign at his/her expense. Prior to the start of Stage 3 construction, the Contractor shall contact Mr. Cacciatore about construction around this sign so that it does not interfere with the operation of his business.
 - * The proposed concrete curb and combination concrete curb and gutter located between Sta. 34+269 and Sta. 34+277 (LT) shall be constructed as shown on Sheet 59 of 389 (of the plans). The proposed sign within this area shall be moved by the property owner prior to the construction of this curb and gutter. The contractor shall contact Mr. Cacciatore approximately two weeks in advance of the construction of the curb and gutter. No cost shall be to the property owner for the installation of the curb and gutter. The property owner shall assume all responsibility of curb and gutter located on his property when this project is finished.
 - * All trees located on the Cacciatore property shall be protected by temporary fence during Stage 3 & 3A construction.
 - * All pruning shall be performed by a professional arborist as stated in Article 201.06 of the Standard Specification Manual.
 - * The sign located within the easement area at Sta. 34+331, 13.2 m LT shall not be disturbed or obstructed during construction.
12. The commitments for the City of Byron are as follows:
- * The BJ Way Clock on the northwest corner of Franklin Street and IL 2 shall remain at its current location.
 - * The Resident Engineer shall contact Chris Mallard of the Byron Fire Department at (815) 234-2361 as soon as possible in regards to the relocation of the Fire Department's signals.
13. Thomas & Laurie Cook would prefer the State place a shallower grade instead of a 1:4 slope. They would allow most of the yard along IL 2 to be regraded as long as their trees are not affected. They also request the State minimize fence removal between their property and St. Mary's Cemetery, if feasible.
14. The fence along Route 2 near Station 33+160 to 33+180 RT shall be repaired if damaged by the Contractor at the Contractor's expense. No cost shall be to the home owner.
15. The Contractor shall remove the pine tree at Sta. 33+567 11m LT at no cost to the home owner.
16. The Resident Engineer shall contact the Byron Fire Department @ 815/234-2361 Ext. 493 as soon as the project begins to have the Fire Department signals relocated.
17. Temporary fencing shall be erected from Station 33+519 to 33+540 Rt. for the protection of children and animals during construction. No cost shall be to the home owner. The Resident Engineer shall give the property owner a 2 week notice prior to installing the temporary fence.
18. Temporary fencing shall be erected from Station 33+540 to 33+570 Rt. for the protection of children and animals during construction. No cost shall be to the home owner. The Resident Engineer shall give the property owner a 2 week notice prior to installing the temporary fence.
19. Temporary fencing shall be erected from Station 33+600 to 33+625 Rt. for the protection of children and animals during construction. No cost shall be to the home owner. The Resident Engineer shall give the property owner a 2 week notice prior to installing the temporary fence.
20. Temporary fencing shall be erected from Station 33+625 to 33+660 Rt. for the protection of children and animals during construction. No cost shall be to the home owner. The Resident Engineer shall give the property owner a 2 week notice prior to installing the temporary fence.
21. The Resident Engineer shall install a 24' private entrance as shown on Plan & Profile Sheet 117 of 389 at Sta. 33+307 (LT).
22. The Resident Engineer shall install depressed curb and gutter on Franklin Street from Sta. 35+950 (LT) to 35+982.5 (LT) to allow for a future project.
23. The Department of Transportation will guarantee the trees at Sta. 33+540 (LT) to be removed if they should happen to die in the future at no cost to the home owner. The home owner would also like trees planted in front of their property in the ROW if at all possible.
24. The commitments for Stillman BancCorp are as follows:
- * The Resident Engineer or Contractor shall inform Stillman BancCorp approximately two weeks in advance of any work to be done to their entrances or parking lots.
 - * Sideroad Entrances along Colfax Street shall be built half at a time, one at a time.
 - * Sideroad Entrances along West Street shall be built one entrance at a time.
 - * When the Contractor is working on Colfax Street, no work shall be done on West Street and it shall be open to traffic with no sideroad road closure and vice versa.
 - * The Contractor shall be allowed to close the mainline entrance along IL 2 (Sta. 33+895) for one week. However, West Street shall be completely open to traffic, with no road closures.
 - * No State or Contractor vehicles shall be allowed to park in the bank parking lot.
 - * Prior to the permanent commercial entrance closure at Sta. 33+874.5, the entrance at Sta. 10+960 Rt. along Colfax Street shall be completely constructed.