

PCC / BITUMINOUS SCHEDULE

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	37R-2	OGLE	389	15
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT #64157				

STATION TO STATION	LENGTH (M)	REMARKS	SURFACE AREA (SQ. M)	BIT. PRIME (MT)	AGG. PRIME (MT)	M4830240 PCC SHOULDERS 240 MM (SQ. M)	M4202245 PCCP 240 MM (JOINTED) (SQ. M)	M3110300 SUB-BASE GRAN MAT TYPE A 300mm (SQ. M)	MX406024 BIT. CONC. SURF. CSE. SUPRPVE. MIX D N70 (50MM) (MTON)	MX408040 INCIDENTAL BIT SURF SUPER (76.2MM) (MTON)	MX408040 INCIDENTAL BIT SURF SUPER (63.5MM) (MTON)	M4400025 BITUMINOUS SURFACE REMOVAL (25.4 MM) (SQ. M)	M4400000 BITUMINOUS SURFACE REMOVAL (SQ. M)	MZ028415 GEOTECHNICAL REINFORCEMENT (SQ. M)	M4402000 PAVEMENT REMOVAL (SQ. M)
09/02/04 BITSCHLD															
MAINLINE															
32 + 604.00 TO 32 + 800.00	196		2019.65	0.48	2.2	945.70	2019.7	3025.1	178.5					3025.1	1945.7
32 + 800.00 TO 32 + 900.00	100		1521.10	0.35	1.7	361.20	1521.1	1912.8	131.7					1912.8	1434.3
32 + 900.00 TO 33 + 000.00	100		1224.30	0.23	1.1	110.40	1224.3	1365.2	86.6					1365.2	783.9
33 + 000.00 TO 33 + 100.00	100		1220.10	0.23	1.1		1220.1	1405.6	86.7					1405.6	731.3
33 + 100.00 TO 33 + 150.00	50		610.10	0.12	0.5		610.1	702.8	43.3					702.8	306.9
33 + 150.00 TO 33 + 200.00	50		610.30	0.12	0.5		610.3	703.0	43.2					703.0	365.2
33 + 200.00 TO 33 + 250.00	50		610.10	0.12	0.5		610.1	702.8	43.2					702.8	365.0
33 + 250.00 TO 33 + 300.00	50		610.10	0.12	0.5		610.1	702.8	43.2					702.8	370.7
33 + 300.00 TO 33 + 350.00	50		604.10	0.11	0.5		604.1	696.8	41.0					696.8	177.9
33 + 350.00 TO 33 + 400.00	50		615.20	0.12	0.6		615.2	707.9	45.0					707.9	360.8
33 + 400.00 TO 33 + 500.00	100		1215.40	0.22	1.0		1215.4	1400.9	81.4					1400.9	694.2
33 + 500.00 TO 33 + 550.00	50		610.10	0.11	0.5		610.1	702.8	40.9					702.8	338.3
33 + 550.00 TO 33 + 650.00	100		1220.00	0.22	1.0		1220.0	1405.5	81.8					1405.5	674.2
33 + 650.00 TO 33 + 700.00	50		610.00	0.11	0.5		610.0	702.7	40.9					702.7	334.0
33 + 700.00 TO 33 + 750.00	50		610.10	0.11	0.5		610.1	702.8	40.9					702.8	344.3
33 + 750.00 TO 33 + 800.00	50		609.80	0.11	0.5		609.8	702.5	40.9					702.5	347.2
33 + 800.00 TO 33 + 950.00	150		2207.50	0.33	1.5		2207.5	2485.7	123.0					2485.7	1024.2
33 + 950.00 TO 34 + 000.00	50		701.30	0.11	0.5		701.3	794.0	40.9					794.0	341.0
34 + 000.00 TO 34 + 300.00	300		3660.20	0.66	3.1		3660.2	4216.6	245.4					4216.6	2035.8
34 + 300.00 TO 34 + 350.00	50		611.40	0.11	0.5		611.4	704.1	40.9					704.1	342.3
34 + 350.00 TO 34 + 400.00	50		687.60	0.11	0.5		687.6	780.3	40.9					780.3	339.7
34 + 400.00 TO 34 + 450.00	50		781.70	0.11	0.5		781.7	874.4	42.9					874.4	324.9
SIDE ROADS															
CREEKSIDE															
0 + 025.90 TO 0 + 027.50	21.6		313.30			80.50	313.3	400.4						400.4	310.3
0 + 011.00 TO 0 + 017.10	6.1	TAPER	190.00	0.04	0.2				15.5						
FOX RUN LANE															
3 + 951.70 TO 3 + 954.80	3.1	BUTT JOINT	27.10	0.07	0.0				7.4			27.1			
3 + 954.80 TO 3 + 974.80	20		178.80	0.49	0.3			215.9	14.1	32.6				215.9	178.4
3 + 974.80 TO 3 + 993.10	18.3		322.10				322.1	356.0						356.0	351.9
3 + 993.00 TO 3 + 999.10	6.1	TAPER		0.02	0.1				8.9						
4 + 006.20 TO 4 + 023.60	17.4		279.10				279.1	311.4						311.4	298.6
4 + 007.00 TO 4 + 013.10	6.1	TAPER		0.04	0.2				13.9						
4 + 023.60 TO 4 + 049.80	26.2		215.80	0.59	0.3			264.4		39.3				264.4	206.1
4 + 049.80 TO 4 + 053.10	3.3	BUTT JOINT	23.40	0.06	0.0					1.4		23.4			
BARRY AVENUE															
4 + 946.00 TO 4 + 950.00	3.2	BUTT JOINT	27.20	0.07	0.0					1.7		27.2			
4 + 950.00 TO 4 + 978.10	28.1		222.40	0.61	0.3			274.5	40.5					274.5	250.4
4 + 978.10 TO 4 + 995.80	17.7		247.80				247.8	280.6						280.6	196.8
PERENE AVENUE															
5 + 936.80 TO 5 + 939.90	3.1	BUTT JOINT	30.30	0.08	0.0					1.8		30.3			
5 + 939.90 TO 5 + 978.00	38.1		343.00	0.94	0.5			413.7	62.5					413.7	300.1
5 + 978.00 TO 5 + 993.70	15.7		266.20				266.2	295.3						295.3	222.0
S. MAPLE AVENUE															
6 + 946.00 TO 6 + 950.00	3.2	BUTT JOINT	18.30	0.05	0.0					1.1		18.3			
6 + 950.00 TO 6 + 978.30	28.3		213.40	0.59	0.3			265.9	38.9					265.9	179.9
6 + 978.30 TO 6 + 993.70	15.4		252.40				252.4	281.0						281.0	144.0
N. MAPLE AVENUE															
7 + 006.20 TO 7 + 012.30	6.1	TAPER		0.04	0.2				15.2						
7 + 006.10 TO 7 + 021.20	15.1		249.80				249.8	277.8						277.8	327.8
7 + 021.20 TO 7 + 059.90	38.7		328.20	0.90	0.5			400.0	59.8					400.0	420.6
7 + 059.90 TO 7 + 062.90	3	BUTT JOINT	25.80	0.07	0.0					1.6		25.8			
SUMNER ST.															
7 + 947.00 TO 7 + 950.00	3	BUTT JOINT	19.20	0.05	0.0					1.2		19.2			
7 + 950.00 TO 7 + 979.80	29.8		225.90	0.62	0.3			281.2	41.2					281.2	191.8
7 + 979.80 TO 7 + 994.00	14.2		238.90				238.9	265.2						265.2	148.8
7 + 993.10 TO 7 + 999.20	6.1	TAPER		0.02	0.1				6.7						
GRANT ST.															
9 + 006.00 TO 9 + 012.10	6.1	TAPER		0.02	0.1				8.5						
9 + 005.90 TO 9 + 017.70	11.8		192.50				192.5	214.4						214.4	175.1
9 + 017.70 TO 9 + 079.90	62.2		427.50	1.17	0.6			542.9	77.9					542.9	356.1
9 + 079.90 TO 9 + 082.90	3	BUTT JOINT	14.80	0.04	0.0					0.9		14.8			
LINCOLN ST.															
9 + 966.80 TO 9 + 969.90	3.1	BUTT JOINT	27.20	0.07	0.0					1.7		27.2			
9 + 969.90 TO 9 + 979.90	10		94.40	0.26	0.1			112.9	17.2					112.9	90.3
9 + 979.90 TO 9 + 993.90	14		248.20				248.2	274.2						274.2	200.9
10 + 005.90 TO 10 + 019.30	13.4		244.20				244.2	269.1						269.1	195.2
10 + 005.70 TO 10 + 011.80	6.1	TAPER		0.02	0.1				8.3						
10 + 019.30 TO 10 + 056.90	37.6		347.40	0.95	0.5			417.1	63.3					417.1	332.8
10 + 056.90 TO 10 + 059.90	3	BUTT JOINT	28.00	0.08	0.0					1.7		28.0			