

LOCATION	LENGTH	AREA	BIT SURF REMOVAL 1.5"	BIT. BASE CSE., SUPER, 8"	BIT. CONC. SURF. CSE., SUPER, MIX "D", N 50	BIT. CONC. BIND. CSE		LEVELING BINDER, (MM), SUPER, N 50 3/4"	BITUMINOUS SHOULDER, SUPERPAVE, 8"	
						9 3/4"	V.D.		SQ YD	SQ YD
	FOOT	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	LT	RT
MAINLINE										
STA 1008+50 - 1010+16.4	166.4	443.7	443.7		37.3				55.5	55.5
STA 1010+16.4 - 1010+31.7	15.3	40.8			4.6				5.1	5.1
STA 1010+31.7 - 1010+80.8	49.1	130.9			14.7		43.1		16.4	16.4
STA 1010+80.8 - 1016+95.4	614.6	1638.9			183.6	894.9			204.9	204.9
STA 1016+95.4 - 1017+52.6	57.2	152.5			17.1		50.2		19.1	19.1
STA 1017+52.6 - 1017+74	21.4	57.1			6.4				7.1	7.1
STA 1017+74 - 1020+50	276	736.0	736.0		61.8				92.0	92.0
RUN-A-ROUND									0.0	0.0
STA 0+00 - 12+87.56		2618.8		2618.8	220.0			25		
SUB-TOTAL			1179.7	2618.8	545.3	894.9	93.3	25.0	400.0	400.0
TOTAL			1180	2619	545	988.1		25	800	

RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION	EACH
STA 1008+50 TO STA 1020+50	16
TOTAL	16

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	EACH
STA 1008+50 TO STA 1020+50	16
TOTAL	16

REMOVAL OF EXISTING STRUCTURE	
LOCATION	EACH
S.N. 055-0024	1
TOTAL	1

TEMPORARY DETOUR DRAINAGE STRUCTURE	
LOCATION	L SUM
STA 6+88 (RUN-A-ROUND)	1
TOTAL	1

BITUMINOUS MATERIALS (PRIME COAT)	
LOCATION	TON
FOG COAT	
MAINLINE	0.31
RUN-A-ROUND	0.34
COLD MILLED SURFACE	
MAINLINE	0.50
TOTAL	1.2

AGGREGATE SURFACE COURSE, TYPE A	
LOCATION	TON
LT STA. 1016+50	22.5
RT STA. 1017+50	23
TOTAL	45

PAVEMENT REMOVAL	
LOCATION	SQ YD
STA 1014+14 TO STA 1014+44	80
STA 1014+66 TO STA 1014+96	80
TOTAL	160

BITUMINOUS SURFACE REMOVAL -BUTT JOINT-	
LOCATION	SQ YD
MAINLINE	
STA 1008+50 - 1008+80	80
STA 1020+20 - 1020+50	80
TOTAL	160.0

DETOUR ROADWAY REMOVAL	
LOCATION	SQ YD
RUN-A-ROUND	
STA 1+50 - 11+50	2619.0
(AREA MEASURED IN CADD)	
TOTAL	2619.0

CONSTRUCTION LAYOUT	
LOCATION	L SUM
STA 1008+50 TO 1020+50	1
TOTAL	1

PAINT SCHEDULE					
LOCATION	TEMP. PAINT PAVEMENT MARKING-line 4"	PAINT PAVEMENT MARKING		SHORT-TERM PAVEMENT MARKING-line 4"	WORK ZONE PAVEMENT MARKING REMOVAL
		WHITE	YELLOW		
	FOOT	FOOT	FOOT	FOOT	SQ YD
RUN-A-ROUND					
RT STA 2+54 - 10+47	786.2				
LT STA 0+00 - 12+87	1284.8				
STA 0+00 - 12+88	2571.6				
MAINLINE					
STA 1008+50 - 1020+50		2400	2400	408	135
SUBTOTAL		2400	2400		
TOTAL	4643	4800		408	135.0

REVISIONS	
NAME	DATE