

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ILL.	04 BRIDGE REP.	PEORIA	15	2
STA. 409+99.00		TO STA. 414+72.02		
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT				

## GENERAL NOTES

*Plan dimensions and details relative to existing structure have been taken from existing plans and are subject to nominal construction variations. It shall be the Contractor's responsibility to verify such dimensions and details in the field and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in the scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.*

*Protective Coat shall not be applied to surfaces to which Waterproofing Membrane System is applied.*

*Prior to pouring the new concrete deck, all loose rust, loose mill scale, and other loose potentially detrimental foreign material shall be removed from the surfaces of the beams or girders in contact with concrete. The cost of this work will be included in the pay item covering removal of the existing concrete. All heavy rust and other tightly adhered potentially detrimental foreign matter shall also be removed from the surfaces of the beams or girders in contact with concrete. Tightly adhered paint may remain unless otherwise noted. This removal shall be accomplished by methods that will not damage the steel. The cost of this work will be paid for according to Article 109.04 of the Standard Specifications.*

PLOT DATE \* DATE \*  
 PLOT SCALE \* SCALE \*  
 REFERENCE \* REF \*

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		GENERAL NOTES  SCALE: VERT. HORIZ. DATE 06-10-2004
DRAWN BY: CEJ		CHECKED BY:
DATE 06-10-2004		