

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	04 BRIDGE REP.	PERIA	14	5
STA. 409+99.08 TO STA. 414+72.02				
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

68420

SCHEDULE OF QUANTITIES

TRAFFIC CONTROL & PROTECTION, STD. 701 402

STA. 409+99.08 TO STA. 414+72.02 = 1.0 EACH

PROTECTIVE SHIELD

PIER #1 SLOPEWALL = 200 SQ. YD.

IMPACT ATTENUATORS, TEMP. (NON-REDIR), TEST LEV 3

JOBSITE = 2 EACH

BITUMINOUS CONCRETE REMOVAL (DECK)

JOBSITE BRIDGE DECK = 1516 SQ. YD.

CONCRETE REMOVAL

PARAPET WALLS & PIER 3 = 8.7 CU. YD.
 N. ABUT. & DECK STA. 409+99.35 = 7.15 CU. YD.
 S. ABUT. & DECK STA. 413+50.23 = 7.15 CU. YD.
 TOTAL = 23.00 CU. YD.

TEMPORARY CONCRETE BARRIER

JOBSITE BRIDGE DECK = 350 FOOT

BAR SPLICERS

ABUTMENTS AND PIER #3 = 38 EACH

STRIP SEAL EXP. JT. ASSY.

N. ABUT. STA. 409+99.35 = 67.34 FOOT
 PIER #3 STA. 412+02.06 = 67.34 FOOT
 S. ABUT. STA. 413+50.23 = 67.34 FOOT
 TOTAL = 202 FOOT

REINFORCEMENT BARS, EPOXY COATED

JOINTS = 3190 POUNDS
 PARAPET = 170 POUNDS
 RAIL POSTS = 20 POUNDS
 TOTAL = 3380 POUNDS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.
 DATE 01-13-2004

DRAWN BY CEJ
 CHECKED BY

PLOT DATE = 01/13/04
 FILE NAME = 011304
 PLOT SCALE = 1/4"=1'-0"
 REFERENCE = 011304