

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
---	---	SANGAMON	44	--2--
STA. -----		TO STA. -----		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- PARK ROADS
- OAK RIDGE CEMTERY INT RDS 2003

GENERAL NOTES:

Where section or Sub-Section Monuments are encountered, the Engineer shall be notified before such monuments are removed. The Contractor shall protect and carefully preserve all property markers and monuments until the owner and authorized Surveyor or Agent has witnessed or otherwise referenced their location.

Any reference to a Standard in the plans shall be interpreted to mean the edition, as indicated by the sub-number listed in the list of Standards, or the copy of the Standard included in these plans.

All details in the plans shall govern construction of this project, and in case of conflict with any Standard drawings included, the said details shall take precedence and shall govern.

The Contractor shall contact J.U.L.I.E. and IHPA Site Manager prior to any excavation to have all public and private utilities located.

The existing signs that interfere with construction shall be relocated as directed by the engineer. After the construction is complete, the contractor shall replace the signs as directed by the engineer. This work will not be paid for separately, but considered included in the contract unit bid prices.

No branch trimming will be permitted unless approval is granted from the IHPA Site Manager and the Resident Engineer.

The following mixture requirements are applicable to this project:

Mixture Use(s)	Level Binder (MM)	Bit. Surface
AC/PG	PG 64-22	PG 64-22
RAP % (max.)	15%	15%
Design Air Voids	4.0% @ N Design = 50	4.0% @ N Design = 50
Mix Composition (Gradation Mixture)	IL 9.5	IL 9.5 or 12.5
Volumetric Requirements	-----	-----
Friction Aggregate	NA	Mix 'C'

COMMITMENTS:

- The Field /Residents Engineer shall contact Studies & Plans concerning any major plan changes to make sure no commitments (not listed) were made affecting the design, and to allow improvements in the design for future projects
- No access will be allowed outside the construction limits without approval of the IHPA Site Manager.
- Roads shall be kept open as much as possible to provide access to the Memorials, Lincoln's Tomb, the Site Office, and Oak Ridge Cemetery. The Contractor shall coordinate all Road Closures/Restriction with the IHPA Site Manager seven calendar days prior to implementation.
- Letter of Understanding with IHPA, City of Springfield, and Oak Ridge Cemetery.
- All excavation within the vicinity of the oak tree at Sta. 11+21, RT. 32.81' (Vietnam Veterans Memorial parking lot stationing) shall be strictly limited so as to avoid any root damage. No branch trimming of this tree will be permitted.

LIST OF STANDARDS

- 000001-04
- 280001-02
- 420001-05
- 420101-02
- 420106-02
- 420701-01
- 442101-05
- 606001-02
- 606201
- 701421-01
- 701422-01
- 701801-03
- 702001-05
- 720001
- 720006
- 720011
- 729001
- 780001-01
- BLR 21-6
- BLR 22-4

DISTRICT SIX	
EXAMINED	<i>Louis J. Harris</i> 20 04
OPERATIONS ENGINEER	

EXAMINED	Oct 27 20 04
<i>W. R. Jones</i>	
PROGRAM IMPLEMENTATION ENGINEER	
EXAMINED	November 4 20 04
<i>William E. North</i>	
PROGRAM DEVELOPMENT ENGINEER	

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		GENERAL NOTES & COMMITMENTS LIST OF STANDARDS
SCALE:	VERT. DATE	HORIZ. DATE
DRAWN BY EJV		CHECKED BY