

• PARK ROADS  
 •• OAK RIDGE CEMETERY INTERNAL ROADS  
 CONTRACT NO. 72774

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK				CONSTRUCTION TYPE CODE		
SUMMARY OF QUANTITIES				URBAN	ROADWAY	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000		
20200100	EARTH EXCAVATION	CU YD	744	744		
25000200	SEEDING, CLASS 2	ACRE	0.3	0.3		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23	23		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23	23		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23	23		
25000710	AGRICULTURAL GROUND LIMESTONE	TON	0.5	0.5		
25100115	MULCH, METHOD 2	ACRE	0.3	0.3		
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	6,490	6,490		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1		
40600300	AGGREGATE (PRIME COAT)	TON	3	3		
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	5,730	5,730		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4"	SQ FT	764	764		

PLOT DATE = 11/4/2004  
 FILE NAME = SCEL  
 REFERENCE = AREP

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES

SCALE: VERT.  
 HORIZ.  
 DATE

DRAWN BY  
 CHECKED BY