

CURB AND/OR GUTTER SCHEDULE

LOCATION	REMOVAL			PROPOSED			
	COMBO. CURB AND GUTTER REMOVAL (LF)	CURB REMOVAL (LF)	GUTTER REMOVAL (LF)	COMBO. CURB & GUTTER 6.24 (LF)	COMBO. CURB & GUTTER 6.06 (LF)	CONC. CURB TYPE B (LF)	CONC. GUTTER TYPE B (LF)
	<u>LINCOLN MEMORIAL DRIVE</u>						
STA 10+19.79 TO STA 11+15.16 RT	100			100			
STA 10+71.24 TO STA 11+15.16 LT	53			53			
STA 11+15.16 TO STA 15+15.17 LT			409				409
STA 11+15.16 TO STA 12+48.89 RT			134				134
STA 12+48.89 TO STA 14+12.08 RT			163				
STA 14+12.08 TO STA 14+71.58 RT			85				60
STA 11+22.46 TO STA 12+80.96 RT	164				164		
STA 11+22.46 TO STA 12+80.96 LT	164				164		
STA 13+90.31 TO STA 14+11.76 RT		28					
STA 13+90.31 TO STA 14+11.76 LT		28					
STA 15+50.11 TO STA 15+77.10 RT			31				31
STA 15+37.18 TO STA 15+77.10 LT			50				50
<u>HONOR ROAD</u>							
STA 60+15.99 TO STA 64+24.29 LT			401				401
STA 60+15.99 TO STA 63+28.01 RT			330				330
STA 63+28.01 TO STA 63+99.39 RT			70		70		
STA 63+99.39 TO STA 64+24.29 RT			22				22
<u>VIETNAM VETERANS MEMORIAL PARKING LOT</u>							
STA 10+24.82 TO STA 11+13.10 LT						117	
STA 10+60.13 TO STA 10+81.32 LT		50				50	
STA 11+01.76 TO STA 12+15.64 LT		100				100	
STA 11+59.08 TO STA 12+88.10 RT		164				164	
STA 12+88.10 TO STA 13+07.45 RT						25	
STA 12+40.14 TO STA 13+55.35 LT		100				100	
STA 13+07.45 TO STA 13+13.50 RT		7				7	
STA 13+42.14 TO STA 14+27.14 RT		164				164	
STA 14+27.14 TO STA 14+46.38 RT						25	
STA 13+79.10 TO STA 14+26.70 LT		41				41	
STA 14+26.70 TO STA 14+29.04 LT		2					
STA 14+27.84 - 15' LT TO 24' LT							9
STA 14+29.04 TO STA 14+95.43 LT		57				57	
STA 14+46.38 TO STA 15+75.46 RT		164				164	
STA 15+27.17 TO STA 16+32.86 LT		100				100	
STA 16+53.26 TO STA 16+73.60 LT		50				50	
STA 16+21.82 TO STA 17+09.50 LT						117	

P. C. C. REMOVAL AND REPLACEMENT SCHEDULE

LOCATION	P. C. C. PAVEMENT REMOVAL (SQ YD)	SUB-BASE GRAN MATL, T-A 4" (SQ YD)	P. C. C. PAVEMENT 8" (SQ YD)
<u>LINCOLN MEMORIAL DRIVE</u>			
STA 10+40.60 TO STA 15+77.10	2,490.0	2,945.0	2,510.0
<u>VIETNAM VETERANS MEMORIAL PARKING LOT</u>			
STA 10+23.00 TO STA 17+11.32	3,042.0	3,340.0	3,042.0
<u>HONOR ROAD</u>			
STA 60+15.99 TO STA 60+65.99	120.0	205.0	120.0
TOTAL =	5,710.0	6,490.0	5,730.0

SIDEWALK REMOVAL

LOCATION	QUANTITY (SQ FT)
<u>VIETNAM VETERANS MEMORIAL PARKING LOT</u>	
STA 10+48.17 TO STA 11+01.53 LT	330.0
STA 16+33.30 TO STA 16+15.33 LT	330.0
TOTAL =	660

REVISIONS	
NAME	DATE

**ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES**

SCALE: VERT. _____
 HORIZ. _____
 DATE _____
 DRAWN BY _____
 CHECKED BY _____

PLOT DATE = 11/4/2004
 PLOT SCALE = SCALE
 REFERENCE = #REF#